

FOR DRIVEWAY DETAILS SEE SHEET 270

\* AREA COMPUTED BY CAD

STREET NAME	SHEET NUMBER	REF. NUMBER	CENTERLINE STATION	SIDE	TYPE R or C	202	PROPOSED DRIVEWAY DIMENSIONS		PROPOSED DRIVEWAY AREA		203				252	301	301	304	304	407	448	452	452	830		
						PAVEMENT REMOVED	APRON AREA	DRIVEWAY AREA	TOTAL RIGID	TOTAL FLEXIBLE	EXCAVATION	EXCAVATION	EXCAVATION	EXCAVATION	FULL DEPTH PAVEMENT SAWING	3 3/4" BITUMINOUS AGGREGATE BASE, PG 64-22	4 3/4" BITUMINOUS AGGREGATE BASE, PG 64-22	8" AGGREGATE BASE AS PER PLAN	10" AGGREGATE BASE AS PER PLAN	BITUMINOUS TACK COAT @ 0.10 GAL PER SQ YD	1 1/4" ASPHALT CONCRETE SURFACE COURSE TYPE 1, PG 64-22	6" PLAIN CONCRETE PAVEMENT	8" PLAIN CONCRETE PAVEMENT	CURB, TYPE 4-B		
							SQ YD	(FEET)	(FEET)	SQ FT	SQ FT	CU YD	CU YD	CU YD											CU YD	CU YD
LANE ROAD		DR-11	14+85	RT	R	-	16 x 10	-	160.0	-		3.0									17.8					
LANE ROAD		DR-12	15+87	RT	R	-	16 x 10	11 x 15	160.0	165.0	2.6	3.0			2.0				1.9	0.7	17.8					
LANE ROAD		DR-13	16+26	RT	C	-	22.98 x 12.5	-	287.2	-			7.1									32.0				
LANE ROAD		DR-14	16+81	LT	C	-	38.31 x 25	-	957.7	-			23.7										106.5			
LANE ROAD		DR-15	16+82	RT	C	-	16.0 x 23.9	-	382.4	-			9.5										42.5			
LANE ROAD		DR-16	17+63	LT	C	-	26.95 x 32	-	862.4	-			21.3										95.9			
US ROUTE 20		DR-1	270+37	RT	C	-	46 x 8	-	368.0	-			9.1										40.9			
US ROUTE 20		DR-2	270+62	LT	R	-	44 x 9	-	396.0	-		7.4											44.0			
US ROUTE 20		DR-1	271+40	RT	C	-	27.88 x 8.5	-	237.0	-			5.9										26.4			
US ROUTE 20		DR-2	272+40	RT	C	-	27.10 x 6.1	-	165.3	-			4.1										18.4			
US ROUTE 20		DR-3	273+90	LT	R	63.00	23.98 x 12.5	20 x 5	299.7	100.0		5.6	2.5				2.5					33.3				
US ROUTE 20		DR-4	275+54	RT	C	-	28.98 x 12.5	-	362.2	-			9.0										40.3			
US ROUTE 20		DR-5	276+00	LT	C	-	38.98 x 12.5	-	487.2	-			12.1										54.2			
US ROUTE 20		DR-6	277+19	RT	R	-	22 x 8.5	15 x 5	187.0	75.0		3.5	1.9				1.9					20.8				
US ROUTE 20		DR-7	277+50	LT	C	-	28.98 x 12.5	-	362.2	-			9.0										40.3			
US ROUTE 20		DR-8	278+00	RT	R	-	17 x 8.5	-	144.5	-		2.7										16.1				
US ROUTE 20		DR-9	278+52	LT	C	-	28.98 x 12.5	-	362.2	-			9.0										40.3			
US ROUTE 20		DR-10	281+37	RT	C	30.00	38.98 x 12.5	-	487.2	-			12.1										54.2			
US ROUTE 20		DR-11	281+68	LT	R	40.89	17.0 x 9.5	-	161.5	-		3.0										18.0				
US ROUTE 20		DR-12	282+33	RT	C	77.33	38.98 x 12.5	35 x 6.5	487.2	227.5		4.2	12.1			3.3			2.5	0.9		54.2				
US ROUTE 20		DR-13	283+51	RT	R	13.33	16 x 10	9 x 24	160.0	216.0		3.0	5.4				5.4					17.8				
US ROUTE 20		DR-14	286+49	LT	R	25.00	16.5 x 9.5	11 x 6	156.75	66.0		2.9	1.6				1.6					17.5				
US ROUTE 20		DR-15	287+08	LT	R	28.00	17.0 x 9.5	11 x 4	161.50	44.0		3.0	1.1				1.1					18.0				
CENTER ROAD		DR-16	6+10	RT	R	-	18 x 10	-	180.0	-		3.4										20.0				
CENTER ROAD		DR-17	6+55	LT	R	-	30 x 10	25 x 4	300.0	100.0		5.6	2.5				2.5					33.4				
CENTER ROAD		DR-18	7+53	RT	R	-	21 x 9.5	19 x 32	199.5	608.0		3.7	15.1				15.1					22.2				
CENTER ROAD		DR-19	8+61	RT	R	-	25 x 9.5	-	237.5	* 1046.0		16.2	4.4			12.2			11.7	4.1		26.4				
CENTER ROAD		DR-20	12+20	RT	R	30.00	16 x 9.5	-	152.0	-		2.9										16.9				
SHEET TOTAL						307.55	SUB-TOTAL				18.8	61.3	174.1			14.2	3.3	30.1			17	6	296	691		
SHEET TOTAL							SHEET TOTAL						255				18		31			17	6	296	691	

H:\98404\DWG\SUBSUM\_DR.DWG - PLOT SCALE: 1=1

CALCULATED  
R.L.B.  
CHECKED  
W.D.B.

DRIVEWAY SUB-SUMMARY

LAK - 20 - 18.72

73  
441