

H:\1998\98404\DWG\QUANT1.DWG PLOT SCALE: 1=1 (9/25/2001)

REF. NO.	STATION		SIDE	ROADWAY												
				202	202	202	202	202	604		608	608		830	830	
				CURB REMOVED	CATCH BASIN REMOVED	MONUMENT ASSEMBLY REMOVED	REMOVAL MISCELLANEOUS SIGN	REMOVAL MISCELLANEOUS BILLBOARD SIGN	MONUMENT ASSEMBLY		4" CONCRETE WALK	DESIGN B, CURB RAMP		CURB, TYPE 6	CURB, TYPE 6 AS PER PLAN	
	FROM	TO		LIN. FT.	EACH	EACH	EACH	EACH	EACH		SQ. FT.	EACH		LIN. FT.	LIN. FT.	
R-1	77+11.25	-	C			1			1							
R-2	77+15.54	-	C			1			1							
R-3	77+38.00	78+10.00	RT	77	1											
R-4	78+00.00	-	LT		1											
R-5	78+00.00	-	RT		1											
R-6	78+33.50	-	RT	128										72		
R-7	78+25.00	-	LT					1								
R-8	78+00.00	-	LT				1									
R-9	75+05.00	-	RT				1									
R-10	78+10.00	-	RT				1									
C-1	77+38.00	78+10.00	RT													72
SW-1	75+00.00	75+39.00	RT								195					
SW-2	75+63.00	75+96.00	RT								165	1				
SW-3	77+10.00	78+12.00	RT								510	2				
SW-4	78+27.00	78+37.00	RT								50					
SW-5	78+55.00	79+00.00	RT	128							225	1				
CR-1	77+21.00		44' LT.										1			
CR-2	78+23.00		49' LT.										1			
TOTALS CARRIED TO ROADWAY SUB-SUMMARY				333	3	2	3	1	2		1145	6		72	72	

REF. NO.	STATION		SIDE	DRAINAGE & EROSION CONTROL													
				603	603	603	603	603	603	603	603	603	604	604	604	604	
				12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	15" CONDUIT, TYPE C	18" CONDUIT, TYPE B	30" CONDUIT, TYPE B	30" CONDUIT, TYPE C	36" CONDUIT, TYPE B	36" CONDUIT, TYPE C		MANHOLE, NO. 3	MANHOLE, NO. 3, AS PER PLAN	CATCH BASIN, NO. 3A	CATCH BASIN, NO. 2-3	
	FROM	TO		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.		EACH	EACH	EACH	EACH	
D-1	75+00.00	75+10.00	LT			5					10						
D-2	75+10.00	76+00.00	LT								90						
D-3	76+00.00	76+04.00	LT & RT				92						2				
D-4	76+00.00	77+85.00	LT								185						
D-5	77+85.00	78+00.00	LT & RT	15	66								1		1	1	
D-6	77+85.00	78+65.00	LT						80								
D-7	78+65.00	78+65.00	LT & RT			5								1	1		
D-8	78+65.00	79+00.00	LT							35							
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				15	66	10	92	80	35	185	100		3	2	3	1	

REF. NO.	SH. NO.	STATION		SIDE	100% LOCAL PARTICIPATION												
					SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL							
					HYDRANT EXTENDED AND ADJUSTED TO GRADE	12" WATER MAIN REMOVED	VALVE BOX ADJUSTED TO GRADE	METER AND BOX RELOCATED	12" DUCTILE IRON LINE VALVE	12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53 WITH PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS							
					EACH	LIN.FT.	EACH	EACH	EACH	EACH	LIN.FT.						
W-1	88	STA. 76+45	LT				1										
W-2	88	STA. 77+68	LT				1										
W-3	88	STA. 77+90	LT				1										
W-4	88	STA. 77+90	LT				1										
W-5	88	STA. 78+22	LT	1													
W-6	88	STA. 78+95	RT						1								
W-7	88	STA. 77+18	RT						1								
W-8	88	STA. 75+00 TO STA. 75+15	LT														15
W-9	88	STA. 75+15 TO STA. 75+32	LT														18
W-10	88	STA. 75+36	LT												1		
W-11	88	STA. 75+00 TO STA. 75+32	LT											32			
TOTALS CARRIED TO WATER SUB-SUMMARY (PG. 312)					1	32	5	1	1								33

CALCULATED A.E.D. CHECKED W.D.B.
 ESTIMATED QUANTITIES
 US ROUTE 20 STA. 75+00 TO STA. 79+00
 LAK - 20 - 18.72
 89
 441