

REF. NO.	STATION		SIDE	ROADWAY										
				202	202	202	202		604		608	608		
				MONUMENT ASSEMBLY REMOVED	CATCH BASIN REMOVED	REMOVAL MISCELLANEOUS: SIGN	REMOVAL MISCELLANEOUS: R.R. TIES		MONUMENT ASSEMBLY		4" CONCRETE WALK,	DESIGN B CURB RAMP		
FROM	TO		EACH	EACH	EACH	LIN.FT.		EACH		EACH	EACH			
R-1	173+57.06	173+57.18	CL.	2					2					
R-2	173+99.57	-	LT.		1									
R-3	173+99.75	-	RT.		1									
R-4	174+35.00	-	RT.			1								
R-5	174+20.00	174+75.00	RT.				70							
SW-1	172+00.00	172+92.00	RT.							445	1			
CR-1	173+27.00		40' LT.								1			
CR-2	174+08.00		37' LT.								1			
CR-3	173+75.00		41' RT.								1			
TOTALS CARRIED TO ROADWAY SUB-SUMMARY				2	2	1	70		2		445	4		

REF. NO.	SH. NO.	STATION		SIDE	100% LOCAL PARTICIPATION				
					SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL
					HYDRANT EXTENDED AND ADJUSTED TO GRADE	HYDRANT ADJUSTED TO GRADE	VALVE BOX ADJUSTED TO GRADE	METER AND BOX RELOCATED	SERVICE STOP BOX ADJUSTED TO GRADE
FROM	TO		EACH	EACH	EACH	EACH	EACH		
W-1	145	STA. 172+98	LT				1		
W-2	145	STA. 173+04	LT				1		
W-3	145	STA. 173+06	LT			1			
W-4	145	STA. 173+04	RT				1		
W-5	145	STA. 173+00	RT	1					
W-6	145	STA. 173+75	LT			1			
TOTALS CARRIED TO WATER SUB-SUMMARY (PG. 312)				1		2	3		

REF. NO.	STATION		SIDE	DRAINAGE & EROSION CONTROL															
				603	603	603	603	603	603	603	603	604	604	604	604	604			
				12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	15" CONDUIT, TYPE C	24" CONDUIT, TYPE B	24" CONDUIT, TYPE C	27" CONDUIT, TYPE B 1500 D-LOAD	27" CONDUIT, TYPE C	30" CONDUIT, TYPE B	MANHOLE, NO. 3	MANHOLE ADJUSTED TO GRADE AS PER PLAN	CATCH BASIN, NO. 3A	MANHOLE, NO. 3 AS PER PLAN	CATCH BASIN, NO. 3	INLET, SIDE DITCH		
FROM	TO		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.		EACH	EACH	EACH	EACH	EACH	EACH		
D-1	172+00.00	172+40.00	LT.							40			1						
D-2	172+40.00	172+40.00	LT. & RT.		60	5							1		2				
D-3	172+40.00	173+30.00	LT.							90			1						
D-4	173+14.62	173+30.00	LT. & RT.								72								
D-5	173+14.62	174+25.00	RT.				110								1				
D-6	174+25.00	174+25.00	RT.			5													
D-7	174+16.80	174+30.00	LT.			45							1	1	1	1			
D-8	174+25.00	174+95.00	RT.					70											
D-9	174+95.00	174+95.00	RT.			5								1	1				
D-10	174+95.00	175+73.00	RT.					78											
D-11	175+73.00	175+73.00	LT. & RT.		73	5								2	1				
D-12	175+73.00	176+00.00	RT.					27											
D-13	172+05.00	172+40.00	LT.	35												1			
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				35	133	65	110	175	90	40	72		2	1	6	4	1	1	