

ROADWAY

REF. NO.	STATION		SIDE	202		203		604																						
	FROM	TO		PIPE REMOVED, 24" AND UNDER	CATCH BASIN REMOVED	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT	MONUMENT ASSEMBLY	LIN. FT.	EACH	CU. YDS.	CU. YDS.	EACH																	
R-1	17+65.79	19+91.92	LT.	220	1																									
R-2	18+29.48	-	CL						1																					
R-3	19+75.30	-	CL						1																					
R-4	17+68.00	19+36.00	LT.			42	42																							
R-5	17+40.00		LT.		1																									
TOTALS CARRIED TO ROADWAY SUB-SUMMARY				220	2	42	42	2																						

DRAINAGE & EROSION CONTROL

REF. NO.	STATION		SIDE	603						604			870																		
	FROM	TO		8" CONDUIT, TYPE C	12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	15" CONDUIT, TYPE C	18" CONDUIT, TYPE B	24" CONDUIT, TYPE B	30" CONDUIT, TYPE B 1250 D-LOAD	MANHOLE, NO. 3	CATCH BASIN, NO. 3	CATCH BASIN, NO. 3A	SEEDING AND MULCHING	SQ. YDS.																
D-1	17+20.00	-	LT. & RT.			37	11																								
D-2	17+20.00	17+42.00	LT.		5			22						2																	
D-3	17+42.00	19+65.74	LT.	12				202						1																	
D-4	20+39.45	21+79.82	LT.											1																	
D-5	19+08.00	-	LT. & RT.			41									2																
D-6	19+08.00	19+65.74	LT.			54																									
E-1	17+68.00	19+36.00	LT.																												
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				12	5	132	11	224	9	144	4	2	2	262																	