

H:\1998\98404\DWG\QUANT3.DWG PLOT SCALE: 1=1 (10/02/2001)

ROADWAY

REF. NO.	STATION		SIDE	202	202	202																		
				CATCH BASIN REMOVED	REMOVAL MISCELLANEOUS: SIGN	REMOVAL MISCELLANEOUS: LANDSCAPE GARDEN																		
	FROM	TO		EACH	EACH	EACH																		
R-1	7+04.00	-	RT.	1																				
R-2	6+80.00	-	LT.		1																			
R-3	7+35.00	-	RT.			1																		
R-4	7+65.00	-	RT.			1																		
TOTALS CARRIED TO ROADWAY SUB-SUMMARY				1	1	2																		

DRAINAGE & EROSION CONTROL

REF. NO.	STATION		SIDE	603	603	603	603	604	604	604	604														
				12" CONDUIT, TYPE B	12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	15" CONDUIT, TYPE C	CATCH BASIN, NO. 3A	MANHOLE, NO. 3 AS PER PLAN	CATCH BASIN, NO. 2-2B	MANHOLE, NO. 3														
	FROM	TO		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH														
D-1	5+70.00	5+70.00	LT. & RT.	44	5			1	1	2															
D-2	7+08.00	7+18.40	LT.			10		1																	
D-3	7+18.00	7+18.40	LT. & RT.	5		35	20	1		1	1														
D-4	7+18.00	7+78.00	RT.				53			1															
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				49	5	45	73	2	1	4	1														

CALCULATED
B.L.B.
CHECKED
W.D.B.

ESTIMATED QUANTITIES
CENTER ROAD, STA. 4+00 TO STA. 8+00

LAK - 20 - 18.72

188
441