

H:\1998\98404\DWG\QUANT3.DWG PLOT SCALE: 1=1 (10/02/2001)

ROADWAY

REF. NO.	STATION		SIDE	202	202																
				FENCE REMOVED	CATCH BASIN REMOVED																
				LIN. FT.	EACH																
	FROM	TO																			
R-1	7+87.00	9+12.00	LT.	125																	
R-2	8+67.00	-	RT.		1																
TOTALS CARRIED TO ROADWAY SUB-SUMMARY				125	1																

DRAINAGE & EROSION CONTROL

REF. NO.	STATION		SIDE	603	603	604	604	604																
				4" CONDUIT, TYPE C	15" CONDUIT, TYPE B	MANHOLE NO. 3	CATCH BASIN NO. 3A	ITEM SPECIAL TRENCH DRAIN																
				LIN.FT.	LIN.FT.	EACH	EACH	LIN. FT.																
	FROM	TO																						
D-1	8+65.00	8+81.00	LT. & RT.	52	43	1	1	16																
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				52	43	1	1	16																

CALCULATED
B.L.L.B.
CHECKED
W.D.B.

ESTIMATED QUANTITIES
CENTER ROAD, STA. 8+00 TO STA. 12+00

LAK - 20 - 18.72

190
441