

H:\1998\98404\DWG\QUANT4.DWG PLOT SCALE: 1=1 (10/02/2001)

REF. NO.	STATION		SIDE	ROADWAY									
				202	202	202	202		608	608		830	
				WALK REMOVED	PIPE REMOVED, 24" AND UNDER	MANHOLE REMOVED	CATCH BASIN REMOVED		4" CONCRETE WALK	DESIGN B CURB RAMP		CURB, TYPE 6	
FROM	TO		SQ. FT.	LIN. FT.	EACH	EACH		SQ. FT.	EACH		LIN.FT.		
R-1	404+22.00	-	LT.				1						
R-2	405+78.00	405+82.50	LT.		5	1	1						
R-3	404+32.00	-	RT.				1						
R-4	405+78.00	-	RT.				1						
R-5	405+43.40	407+00.00	RT.	658									
SW-1	405+48.61	407+00.00	RT.						484	2			
CR-1	404+58.00		39' RT.								1		
CR-2	404+73.00		30' LT.								1		
CR-3	405+10.00		42' LT.								1		
CR-4	405+90.00		41' LT.								1		
C-1	405+50.00	407+00.00	RT.									156	
TOTALS CARRIED TO ROADWAY SUB-SUMMARY				658	5	1	4		484	6		156	

DRAINAGE & EROSION CONTROL

REF. NO.	STATION		SIDE	DRAINAGE & EROSION CONTROL																	
				603	603	603		604	604	604											
				15" CONDUIT, TYPE B	18" CONDUIT, TYPE B	24" CONDUIT, TYPE B		MANHOLE, NO. 3	MANHOLE, NO. 3 AS PER PLAN	CATCH BASIN, NO. 3A											
FROM	TO		LIN. FT.	LIN. FT.	LIN. FT.		EACH	EACH	EACH												
D-1	403+00.00	404+32.00	LT.			132															
D-2	404+32.00	-	LT.	5																	
D-3	404+32.00	405+52.00	LT.		120			1													
D-4	405+52.00	406+02.00	LT.	53				1													
D-5	406+02.00	-	LT.	8																	
D-6	406+02.00	407+00.00	LT.	95																	
D-7	404+32.00	-	LT. & RT.	54																	
D-8	406+02.00	-	LT. & RT.	54																	
TOTALS CARRIED TO DRAINAGE SUB-SUMMARY				269	120	132		2	1	4											

REF. NO.	SH. NO.	STATION	SIDE	100% LOCAL PARTICIPATION				
				SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL
				HYDRANT EXTENDED AND ADJUSTED TO GRADE	HYDRANT ADJUSTED TO GRADE	VALVE BOX ADJUSTED TO GRADE	METER AND BOX RELOCATED	SERVICE STOP BOX ADJUSTED TO GRADE
				EACH	EACH	EACH	EACH	EACH
W-1	204	STA. 403+53	RT				1	
W-2	204	STA. 405+57	LT			1		
W-3	204	STA. 405+62	LT			1		
W-4	204	STA. 405+65	LT			1		
TOTALS CARRIED TO WATER SUB-SUMMARY (PG. 312)						3	1	