* FOR INFORMATION ONLY

WATERWORKS		100% LOCAL PARTICIPATION – LAKE COUNTY DEPARTMENT OF UTILITIES																					
		SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	*	638	SPECIAL	SPECIAL	638	SPECIAL	638	638	638	638	SPECIAL	202	
SHEET	W/L STATION LIMITS	HYDRANT EXTENDED AND ADJUSTED TO GRADE	VALVE BOX ADJUSTED TO GRADE	METER AND BOX RELOCATED	8" WATER MAIN DUCTILE IRON PIPE, ANSI CLASS 53 WITH PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS	10" WATER MAIN DUCTILE IRON PIPE, ANSI CLASS 53 WITH PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS	12" WATER MAIN DUCTILE IRON PIPE, ANSI CLASS 53 WITH PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS	8" GATE VALVE WITH VALVE BOX	10" GATE VALVE WITH VALVE BOX	12" GATE VALVE WITH VALVE BOX	BLOW-OFF ASSEMBLY	BULKHEAD ABANDONED PIPE	WATERWORK, MISC.: CUT-IN-TEE, 12"x10"	6" HYDRANT ASSEMBLY, TYPE B	HYDRANT REMOVED FOR STORAGE	WATERWORK, MISC.: CUT-IN-TEE, 8"x6"	16"x12" TAPPING SLEEVE VALVE WITH VALVE BOX	WATERWORK, MISC.: CUT-IN-TEE, 10"x6"	WATERWORK, MISC.: CUT-IN-TEE, 8"x8"	WATERWORK, MISC.: CUT-IN-TEE, 12"x12"	WATERWORK, MISC.: CUT-IN-TEE, 10"x10"	6" HYDRANT ASSEMBLY, TYPE A	12" WATER MAIN REMOVED	
		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	LIN. FT.	
310	BOWHALL ROAD STA. 6+00 TO 10+00			3		382			1			1	1	1	1									
310	BOWHALL ROAD STA. 2+00 TO 6+00					93			1		1	1			1			1			1	1		
310	HALE ROAD			1			285			2	1	2								2				
310	LEE ROAD				62			2				1							1					
311	TOWNLINE ROAD STA. 7+00 TO STA. 10+00						222			1	1			1	2					1				
311	TOWNLINE ROAD STA. 3+00 TO STA. 7+00	1					104			1		1								1				
311	GREEN ROAD						174			2	1	2					1			1				
87	US ROUTE 20		1	1			273																	
89	US ROUTE 20	1	5	1			33																272	
91	US ROUTE 20	1	1							1													32	
93	US ROUTE 20	1		1																				
95	US ROUTE 20		3	2											1	1						1		
97	US ROUTE 20	1	1	5																				
99	US ROUTE 20			1																				
144	US ROUTE 20	1																						
146	US ROUTE 20	1	2	3																				
148	US ROUTE 20	1	1																					
150	US ROUTE 20						17																	
170	US ROUTE 20	1																						
172	US ROUTE 20	1	3																					
205	US ROUTE 20		3	1																				
	GRAND TOTALS	10	20	19	62	475	1108	2	2	7	4	8	1	2	5	1	1	1	1	5	1	2	304	

FOR PLAN VIEWS SEE SHEETS 304 THRU 309
FOR WATERWORK DETAILS SEE SHEETS 313 THRU 315

CALCULATED XXX
CHECKED XXX

WATER MAIN IMPROVEMENTS SUB-SUMMARY

LAK-20-18.72

312
441

H:\1998\98404\DWG\WATERSUM.DWG – PLOT SCALE = 1:1