

INTERCONNECT QUANTITIES

CALC. BY: _____	LAKE COUNTY LAK-20-2.70	OHIO
DATE: _____		FHWA REGION 5
CHKD. BY: _____		FEDERAL PROJECT
DATE: _____		

92
98

100% CITY

S.O.M.(S.R.91) & RIDGE RD. (S.R.84)						
INTERSECTION	CONNECTION	POLE NO.	6 PAIR PE-39 QTY (IN FT.)	6 PAIR PE-38 QTY (IN FT.)	6 PAIR PE-39 QTY (IN FT.)	6 PAIR PE-38 QTY (IN FT.)
HALLE DRIVE/PARLANE	CONTROLLER		0			
	TOP OF POLE W/2" CONDUIT RISER	801490	48			
	POLE	801491		128		
	POLE	697190		130		
MAPLEGROVE ROAD	TOP OF POLE W/2" CONDUIT RISER	UNKNOWN		140		
	PULL BOX NO. 2		28			
	PULL BOX NO. 3		38			
	PULL BOX NO. 4		56			
	PULL BOX NO. 5		52			
	PULL BOX NO. 6		47			
	PULL BOX NO. 1		60			
	CONTROLLER		20			
	TOP OF POLE W/2" CONDUIT RISER	639549	129			
	POLE	673629		122		
	TOP OF POLE W/2" CONDUIT RISER	639549		122		
S.O.M. CENTER RD (S.R.91)	PROP. PULL BOX NO. 11		142			
	PULL BOX NO. 2		64			
	PULL BOX NO. 3		52			
	PULL BOX NO. 4		38			
	PULL BOX NO. 1		105			
	CONTROLLER		21			
	TOP OF POLE W/2" CONDUIT RISER	349246	47			
	POLE	247208		123		
	POLE	319333		120		
	TOP OF POLE W/2" CONDUIT RISER	261872		133		
	MAPLEGROVE ROAD	CONTROLLER		88		
CONTROLLER			0			
PULL BOX NO. 1			21			
PULL BOX NO. 6			91			
MAPLEGROVE ROAD	TOP OF POLE W/2" CONDUIT RISER	UNKNOWN	178			
	POLE	303714		163		
	TOP OF POLE W/2" CONDUIT RISER	303715		163		
HALLE DRIVE	PULL BOX NO. 1		38			
	PULL BOX NO. 2		17			
	PULL BOX NO. 3		27			
	CONTROLLER		26			

100% CITY

S.O.M.(S.R.91) & RIDGE RD. (S.R.84)						
INTERSECTION	CONNECTION	POLE NO.	6 PAIR PE-39 QTY (IN FT.)	6 PAIR PE-38 QTY (IN FT.)	6 PAIR PE-39 QTY (IN FT.)	6 PAIR PE-38 QTY (IN FT.)
COLONIAL BLVD	PULL BOX NO. 3				26	
	PULL BOX NO. 2				27	
	PULL BOX NO. 4				75	
	TOP OF POLE W/2" CONDUIT RISER	UNKNOWN			108	
	POLE	308383				154
	POLE	UNKNOWN				170
	POLE	325141				141
	POLE	311417				142
	POLE	311416				138
	POLE	603510				143
	POLE	UNKNOWN				135
COLONIAL BLVD	POLE	328348				135
	POLE	30-198				135
	TOP OF POLE W/2" CONDUIT RISER	311415				124
	PULL BOX NO. 1				81	
	CONTROLLER				20	
TOTALS TO SHEET 93			1433	1344	337	1417

NOTE:
A QUANTITY OF 2563 LIN. FT. FOR REMOVAL OF EXISTING INTERCONNECT HAS BEEN TRANSFERRED TO SHEET 93