



CURB TRANSITION
Transition curb from a height of 2' to the proposed height of 6" in ten linear feet.

* NOTE: SPECIAL CASTING SHALL BE A NEENAH #R-3250 WITH 6" TAPER CURB

Existing drive apron to be removed under item 202 Sidewalk removed.

STATION		201		202		203	
FROM	TO	STUMP REMOVED 18"	STUMP REMOVED 60"	SIDEWALK REMOVED	CURB REMOVED	WEARING COURSE REMOVED	EXCAVATION NOT INCLUDING EMBANKMENT
560+61	564+50	L	2	2135	389	44	
560+98	564+50	R		1584	352	39	
TOTALS			2	3719	741	83	284

STATION		PAVEMENT					
FROM	TO	301	310	403	404	408	609
560+61	564+50	L	37	24	14	7	389
560+98	564+50	R	35	22	12	6	352
TOTALS			72	46	26	13	741

EROSION CONTROL		
659		
COMMERCIAL FERTILIZER	AGRI-CULTURAL LIMING	SEEDING AND MULCHING
TONS	TONS	SQ. YDS.
.08	.42	933

DRAINAGE					
STATION	SIDE	202	603	604	604
		CATCH BASIN ABANDONED	12" CONDUIT	M.H. RECON-STRUCTED TO GRADE WITH SPEC. CASTING	STANDARD Nº 5-A CATCH BASIN
562+41	L	1	5		1
562+41	R	1			
562+43	R			1	
TOTALS		2	5	1	1

**NORTH RIDGE ROAD
U.S. 20- WEST APPROACH**