SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
2	4	7	8	13	20	23	24	25	28							
															ROADWAY	
			400								202	32000	400	METER	CURB REMOVED	
								2775			202	54000	2775	EACH	RAISED PAVEMENT MARKER REMOVED	
			1								202	98100	1	EACH	REMOVAL MISC.: HEADWALL	8
			78								203	12000	78	CU. METER	EXCAVATION, NOT INCLUDING EMBANKMENT CONSTRUCTION	
			425								203	60101	425	METER	LINEAR GRADING, AS PER PLAN	8
	20										604	39501	20	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	4
	5										604	39600	5	EACH	MONUMENT BOX RECONSTRUCTED TO GRADE	
															DRAINAGE	
			0.39								602	20000	0.39	CU. METER	CONCRETE MASONRY	
			3.65								603	10600	3.65	METER	600 MM CONDUIT, TYPE C, 706.01	
	100										604	09001	100	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	4
	100										604	09500	100	EACH	CATCH BASIN RECONSTRUCTED TO GRADE	
	25000										SPECIAL	60450000	25000	KG	MISCELLANEOUS METAL	4
															PAVEMENT	
	2500										252	01000	2500	SQ. METER	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT	
	5000										253	01000	5000	SQ. METER	PAVEMENT REPAIR	
			905	249632							254	01000	250537	SQ. METER	PAVEMENT PLANING, BITUMINOUS	
			222.6								301	46000	222.6	CU. METER	ASPHALT CONCRETE BASE, PG 64-22	
			420	37445							407	10000	37865	LITER	TACK COAT	
				9486							448	30020	9486	CU. METER	ASPHALT CONCRETE SURFACE COURSE, 9.5 mm, PG 64-22	5
			99.1								448	46050	99.1	CU. METER	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22	
			400								609	26000	400	METER	CURB, TYPE 6	
															TRAFFIC CONTROL	
								1234			621	00200	1234	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY	
								1541			621	00300	1541	EACH	PRISMATIC RETROREFLECTOR	
								1541			621	00600	1541	EACH	RAISED PAVEMENT MARKER CASTING, INSTALLATION ONLY	
		25									625	25100	25	METER	CONDUIT, 25 MM, 713.04	
		25									625	29000	25	METER	TRENCH	
		1									625	30500	1	EACH	PULLBOX, 713.09, 450 MM	
							26				632	26500	26	EACH	DETECTOR LOOP	
		26									632	27200	26	EACH	LOOP DETECTOR TIE IN	
		25									632	65200	25	METER	LOOP DETECTOR LEAD IN CABLE	
									1		SPECIAL	69098000	1	EACH	ROADWAY MISC.: ROADWAY MOUNTED E SENSOR	27
									1		SPECIAL	69098000	1	EACH	ROADWAY MISC.: CABLE SPLICE KIT	27
						2.19					SPECIAL	69080000	2.19	KM	PAVEMENT MARKING MISC: EDGE LINE	9-11
				36.68		0.42					SPECIAL	69080000	37.1	KM	PAVEMENT MARKING MISC: LANE LINE	9-11
				18.58		0.47					SPECIAL	69080000	19.05	KM	PAVEMENT MARKING MISC: CENTER LINE	9-11
						468					SPECIAL	69080010	468	METER	PAVEMENT MARKING MISC: CHANNELIZING LINE	9-11
				96.5							SPECIAL	69080010	96.5	METER	PAVEMENT MARKING MISC: STOP LINE	9-11
				24.4							SPECIAL	69080010	24.4	METER	PAVEMENT MARKING MISC: CROSSWALK LINE	9-11
						222					SPECIAL	69080010	222	METER	PAVEMENT MARKING MISC: TRANSVERSE LINE	9-11
															MAINTENANCE OF TRAFFIC	
		205									410	12000	205	CU. METER	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
		48									614	11100	48	HOURS	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
		30									614	12460	30	EACH	WORK ZONE MARKING SIGN	
		100									614	13000	100	CU. METER	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
		36.82									614	20100	36.82	KM	TEMPORARY LANE LINE, CLASS I, 642 PAINT	
		36.82									614	20500	36.82	KM	TEMPORARY LANE LINE, CLASS II, 642 PAINT	
		19.34									614	21100	19.34	KM	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
		19.34									614	21500	19.34	KM	TEMPORARY CENTER LINE, CLASS II, 642 PAINT	
		488									614	23200	488	METER	TEMPORARY CHANNELIZING LINE, CLASS I, 642 PAINT	
		222									614	25200	222	METER	TEMPORARY TRANSVERSE LINE, CLASS I, 642 PAINT	
		97									614	26200	97	METER	TEMPORARY STOP LINE, CLASS I, 642 PAINT	
		25									614	27200	25	METER	TEMPORARY CROSSWALK LINE, CLASS I, 642 PAINT	
		20									616	10000	20	CU. METER	WATER	
		1									616	20000	1	M. TON	CALCIUM CHLORIDE	
											614	11000	LUMP		MAINTAINING TRAFFIC	
											623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
											624	10000	LUMP		MOBILIZATION	
											806	26000	13	MONTH	COMPUTER EQUIPMENT FOR FIELD OFFICE	

CALCULATED

CHECKED

GENERAL SUMMARY

LAK-20-28.014

12
28

PLOT SUBMITTED: 11-FEB-1998 15:38

PLOTTED BY: coop2
PLOTTED FROM: /users/bilorincz/pid1698/b1698lgsa.dgn

filename.dgn