

FHWA REGION	STATE	PROJECT
5	OHIO	

LAKE COUNTY  
 LAK-20-29.76

PLAN NO. BR-55-84

# GENERAL NOTES

ITEM 606 - BRIDGE TERMINAL ASSEMBLY, STD. TYPE B MODIFIED AS PER PLAN

PAYMENT FOR THIS ITEM SHALL INCLUDE THE COST OF THE ADDITIONAL ENCASED STEEL POST AS SHOWN ON SHEET 6.

ITEM 619 - FIELD OFFICE

THE CONTRACTOR SHALL PROVIDE A SUITABLE FIELD OFFICE HAVING A MINIMUM OF 150 SQ. FT. OF FLOOR SPACE. PAYMENT SHALL BE AT THE LUMP SUM PRICE BID FOR ITEM 619, FIELD OFFICE.

ITEM 622 - TEMPORARY CONCRETE BARRIER

THE TEMPORARY BARRIER SHALL BE PIN-CONNECTED AND HAVE TAPERED END TERMINALS. THE BARRIER SHALL BE PLACED AS SHOWN IN THESE PLANS BEFORE ANY REMOVAL OPERATIONS BEGIN. THE BARRIER SECTIONS WILL REMAIN THE PROPERTY OF THE CONTRACTOR AND BE REMOVED FROM THE SITE BY HIM AT THE COMPLETION OF THE PROJECT. MEASUREMENT SHALL BE BASED UPON THE LENGTH OF BARRIER INSTALLED UNDER EACH MAINTENANCE OF TRAFFIC PHASE.

ITEM SPECIAL - CHANNEL CLEANOUT

THIS WORK SHALL BE DONE IN ACCORDANCE WITH ITEM 203 OF THE OMS. ALL REMOVAL SHALL CONFORM TO THE LINES, GRADES, AND ELEVATIONS SHOWN ON THE PLANS. PAYMENT WILL BE MADE AT THE CONTRACT BID PRICE FOR ITEM SPECIAL - LUMP SUM - CHANNEL CLEANOUT.

UTILITIES

THE LOCATIONS OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS OF THE UTILITY AS REQUIRED BY SECTION 153.64 ORC.

AT LEAST TWO WORKING DAYS PRIOR TO COMMENCING CONSTRUCTION OPERATIONS IN AN AREA WHICH MAY INVOLVE UNDERGROUND UTILITIES, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER, THE REGISTERED UTILITY PROTECTION SERVICE AND THE OWNERS OF THE UNDERGROUND UTILITIES SHOWN IN THE PLANS.

THE OWNER OF THE UNDERGROUND UTILITY FACILITY SHALL, WITHIN FORTY-EIGHT HOURS, EXCLUDING SATURDAYS, SUNDAYS AND LEGAL HOLIDAYS, AFTER NOTICE IS RECEIVED, STAKE, MARK OR OTHERWISE DESIGNATE THE LOCATION OF THE UNDERGROUND UTILITIES IN THE CONSTRUCTION AREA IN SUCH A MANNER AS TO INDICATE THE COURSE TOGETHER WITH APPROXIMATE DEPTH AT WHICH IT WAS INSTALLED. THE MARKING OR LOCATION SHALL BE COORDINATED TO STAY APPROXIMATELY TWO DAYS AHEAD OF THE PLANNED CONSTRUCTION.

THE FOLLOWING UNDERGROUND UTILITIES AND OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT:

EAST OHIO GAS COMPANY 1010 WEST 30TH STREET ASHTABULA, OHIO 44004 PHONE: (216) 992-6008	OHIO BELL TELEPHONE COMPANY 820 W. SUPERIOR AVENUE ROOM 215 CLEVELAND, OHIO 44114 PHONE: (216) 822-6241
--	--

THE WESTERN RESERVE TELEPHONE COMPANY  
 4616 PARK AVENUE  
 ASHTABULA, OHIO 44004  
 PHONE: (216) 352-9361

THE FOLLOWING AERIAL UTILITIES ARE LOCATED WITHIN THE WORK LIMITS OF THE PROJECT. THE CONTRACTOR SHALL ALSO NOTIFY THESE UTILITY COMPANIES AT LEAST 48 HOURS PRIOR TO COMMENCING CONSTRUCTION OPERATIONS.

CLEVELAND ELECTRIC ILLUMINATING COMPANY 2210 SOUTH RIDGE ROAD ASHTABULA, OHIO 44004 PHONE: (216) 998-5151	THE WESTERN RESERVE TELEPHONE COMPANY 4616 PARK AVENUE ASHTABULA, OHIO 44004 PHONE: (216) 352-9361
--	---

RAISED PAVEMENT MARKER TREATMENT

RAISED PAVEMENT MARKER (RETRO-REFLECTORS AND CASTINGS) REMOVAL FROM THE BRIDGE DECK SHALL BE PAID FOR UNDER ITEM 202 - WEARING COURSE REMOVED. THESE RAISED PAVEMENT MARKERS SHALL NOT BE REPLACED.

RAISED PAVEMENT MARKER PRISMATIC RETRO-REFLECTORS WHICH CONFLICT WITH THE MAINTENANCE OF TRAFFIC SCHEMES WITHIN THE EXISTING PAVEMENT MARKING REMOVAL LIMITS SHALL BE REMOVED AND REPLACED ACCORDING TO THE NOTES ON SHEET 5. THE FOLLOWING ESTIMATED QUANTITY IS INCLUDED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER TO PERFORM THIS WORK ON ALL PARTS OF THIS PROJECT.

ITEM SPECIAL - PRISMATIC RETRO-REFLECTOR REPLACED 116 EACH

ITEM SPECIAL - PAVEMENT PLANING, BITUMINOUS, WITHOUT HEAT

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER TO REMOVE EXISTING ASPHALT CONCRETE ON THE APPROACH PAVEMENT AS REQUIRED TO PROVIDE A SMOOTH TRANSITION. SEE NOTE ON SHEET 2. ITEM 404 ASPHALT CONCRETE AC-20.

ITEM SPECIAL - PAVEMENT PLANING, BITUMINOUS, WITHOUT HEAT 245 SQ. YDS.

ITEM 407 - TACK COAT

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER ON THE APPROACH PAVEMENT.

ITEM 407 - TACK COAT 25 GALLONS

MICROFIL  
 OCT 3 1986