



SAMPLING DETECTOR ESTIMATED QUANTITIES

QUANT.	UNIT	ITEM	DESCRIPTION
8	EA.	625	10 Channel Encoder
8	EA.	625	Loop Detector Amplifier
4	EA.	625	Signal Control Cabinet, 1.9 C.F.
100	L.F.	625	Power Cable 3/8" No. 8 AWG Stranded RHW or RHW Type
1000	L.F.	625	Loop Detector Wire, No. 14 AWG, RHW or RHW Type
350	L.F.	625	Loop Detector Lead In Cable, 2/c No. 14 AWG, Twisted Pair, Shielded
4	EA.	625	Ground Rod
4	EA.	625	Pull Box 18" Circular 713.09, As Per Plan
400	L.F.	625	Loop Detector Pavement Cutting
310	L.F.	625	Conduit 2" 713.04 Type III
310	L.F.	625	Trench
4	EA.	625	Weatherhead And Conduit Riser
4	EA.	625	Power Service

CALC: P.C.S. 4-73
CHK: L.T.V. 4-73