

CALC: PCB 9-83
CHK: ROB 9-83

LEGEND

- 8" ITEM 462
- 10" ITEM 304
- ITEM 202 - WALK REMOVED
- ITEM 202 - WEARING COURSE REMOVED
- 1" ITEM 404 ON 5" ITEM 301
- ITEM 404 FEATHER

20' ±

1" ASPHALT CONCRETE
5" MACADEM ON SAND SUB-GRADE

EXISTING TYPICAL-MIDLAND AVENUE

CALCULATIONS

R-4 (37x5) = 185 S.F.
R-1 1/2(21x5) = 52.5 S.F.
R-6 (5x5) = 25 S.F.

- NOTES:**
- FOR STORM SEWER PROFILES SEE SHEET NO. 77.
 - FOR PAVEMENT, DRIVE, SIDEWALK, CURB & CUTTER QUANTITIES SEE CALCULATIONS SHEET NO. 15.
 - FOR PAVEMENT DETAIL SEE SHEET NO. 13.
 - FOR CROSS SECTIONS SEE SHEET NO. 49.
 - FOR DRIVE DETAIL SEE SHEET NO. 22.
 - (*) TO BE REMOVED UNDER ITEM 201 CLEARING AND GRUBBING

Excavation 227 C.Y.
Embankment 118 C.Y.
Sodding 475 S.Y.

REF.	STATION TO STATION	SIDE	202		202	604		
			STRUCTURE REMOVED	WALK REMOVED	CATCH BASIN REMOVED	SANITARY MANHOLE ADJUSTED TO GRADE		
D-1	72+04.6	RT.	LUMP	S.F.	EA.	EA.		
R-1	72+19 TO 72+40	RT.		53				
R-2	70+33	LT.	LUMP					
R-4	70+92 TO 71+34	RT.		185				
R-5	73+64	RT.						
R-6	73+93 TO 73+98	RT.		25				
TOTALS			LUMP	263	1	1		