

ANJAC CORPORATION

1 Sty. Brick & Block JUC PARTNERSHIP

ARMOND BERK & NANCY BERK

FHWA REGION	STATE	PROJECT
5	OHIO	

37  
114

LAKE COUNTY  
LAK-20-6.65

CALC: PCB 9-83  
CHK: ROB 9-83

LEGEND

- 8" ITEM 452
  - 1" ITEM 404 ON 5" ITEM 301
  - ITEM 202 - PAVEMENT REMOVED
  - ITEM 202 - WALK REMOVED
  - ITEM 202 - WEARING COURSE REMOVED
  - ITEM 304 - 10" AGGREGATE BASE 19'±
- 2" ASPHALT CONCRETE    6" MACADAM ON SAND SUB-BASE

EXISTING TYPICAL MIDDLESEX ROAD

CALCULATIONS

- R-4 (400 x 5) = 2000 S.F.
- R-6 [(15.5 x 14) + (16 x 17)] ÷ 9 = 54.3 S.F.
- R-7 [(34.5 x 13.5) + (16.5 x 4)] ÷ 9 = 126.9 S.F.
- R-8 (5 x 9) = 45 S.F.
- R-10 (5 x 24) = 120 S.F.
- R-11 (5 x 12) = 60 S.F.
- R-12 (7 x 1.5) = 10.5 S.F.

NOTES:

1. FOR STORM SEWER PROFILES SEE SHEET NO. 79.
2. FOR PAVEMENT DETAILS SEE SHEET NO. 75.
3. FOR PAVEMENT, DRIVE, SIDEWALK, CURB & GUTTER QUANTITIES SEE CALCULATIONS SHEET NO. 16.
4. FOR CROSS SECTIONS SEE SHEET NO. 55-56.
5. FOR DRIVE DETAIL SEE SHEET NO. 22.
6. \* TO BE REMOVED UNDER ITEM 201 CLEARING AND GRUBBING
7. REMOVE R-5 TO 56' LEFT OF CENTERLINE.
8. FOR SANITARY NOTES AND DETAIL SEE SHEET NO. 22A.

Excavation	286 C.Y.
Embankment	52 C.Y.
Sodding	408 S.Y.

\* W/706.11 JOINTS

Ref	Station to Station	Side	PAVEMENT REMOVED		CONCRETE FOUNDATION REMOVED		PORTIONS OF STRUCTURE REMOVED		604 MANHOLE AS PER PLAN		604 SANITARY MANHOLE ADJUSTED TO GRADE	
			S.Y.	S.F.	EA.	LUMP EA.	EA.	EA.				
D-1	99+45	LT.							1			
D-2	98+87	RT.								1		
R-1	100+91	LT.										
R-2	100+96.5	RT.										
R-3	101+77.5	RT.										
R-4	98+00 TO 102+00	LT.		2000								
R-5	100+00 TO 101+00	LT.					LUMP					
R-6	98+00 TO 98+18.5	RT.	54.3									
R-7	98+27 TO 98+76	RT.	126.9									
R-8	98+00 TO 98+09	RT.		45								
R-9	100+97	LT.										
R-10	99+36 TO 99+60	RT.		120								
R-11	101+82 TO 102+00	RT.		60								
R-12	101+27	LT.		10.5								
TOTALS			181	2236	1	LUMP	3		1		1	