

THE CITIZENS SAVINGS & LOAN CO.

G. SUMNER & MARY L. STILWELL

CAPCO ENTERPRISES CO.

FHWA REGION	STATE	PROJECT
5	OHIO	

40  
114

LAKE COUNTY  
LAK-20-6.65

CALC: PGB 9-83  
CHK: ROB 9-83

LEGEND

- 8" ITEM 452
- 1" ITEM 404 ON 5" ITEM 301
- ITEM 202 - PAVEMENT REMOVED
- ITEM 202 - WALK REMOVED
- ITEM 202 - WEARING COURSE REMOVED

CALCULATIONS

- R-6 (51.5 x 5.4) ÷ 9 = 30.9 S.F.
- R-7 (400 x 5) = 2000 S.F.
- R-8 (27.5 x 6) ÷ 9 = 18.3 S.F.
- R-9 (29.0 x 6) ÷ 9 = 19.3 S.F.
- R-10 (252 x 5) = 1260 S.F.

NOTES:

1. FOR SANITARY NOTES AND DETAILS SEE SHEET NO. 22A.
2. FOR STORM SEWER PROFILES SEE SHEET NO. 79.
3. FOR PAVEMENT DETAILS SEE SHEET NO. 75.
4. FOR PAVEMENT, DRIVE, SIDEWALK, CURB+GUTTER QUANTITIES SEE CALCULATIONS' SEE SHEET NO. 17.
5. FOR CROSS SECTIONS SEE SHEET NO. 59-60.
6. FOR DRIVE DETAILS SEE SHEET NO. 22.
7. \* TO BE REMOVED UNDER ITEM 201 CLEARING AND GRUBBING

\* W/706.11 JOINTS

REF.	STATION TO STATION	SIDE	202					NO. 3 MANHOLE AS PER PLAN	CONCRETE BARRIER TYPE "D"
			CATCH BASIN REMOVED	PIPE REMOVED 24" & UNDER	PAVEMENT REMOVED	WALK REMOVED	CURBS REMOVED		
D-1	112+90.7	LT.							
R-1	110+50	LT.							
R-2	110+50	RT.							
R-3	113+01	RT.							
R-4	113+75	LT.							
R-5	113+75	RT.		20					
R-6	112+00 TO 112+56	LT.			30.9				
R-7	110+00 TO 114+00	LT.				2000			
R-8	110+00 TO 110+29	LT.			18.3				
R-9	110+68 TO 111+01	LT.			19.3				
R-10	110+00 TO 112+53	RT.				1260			
R-11	111+82	LT.					6		
R-12	110+77 TO 110+95	RT.					25		
R-13	111+19 TO 111+40	RT.					34		
R-14	111+61 TO 111+70	RT.					20		
R-15	111+85 TO 112+03	RT.					20		
R-16	112+94 TO 114+00	RT.					127		
R-17	111+28 TO 114+00	LT.					272		
R-18	111+22	LT.					6		
R-19	111+56	LT.					6		
15-P	110+77 TO 110+95	RT.						18	
16-P	111+19 TO 111+69	RT.						50	
TOTALS			5	20	69	3260	516	1	68

Excavation 166 C.Y.  
Embankment 164 C.Y.  
Sodding 259 S.Y.

