

GENERAL SUMMARY - TRAFFIC CONTROL

--	--	--	--

LAKE COUNTY
LAK-20-6.65

81
114

1
13

①-GENERAL NOTES					①-IX FUNDS		②-LOCAL FUNDS			
ROADWAY-SHEET NOS.					PARTICIPATION					
①	6	7	8	9+	①	②+	TOT.	UNIT	ITEM	ITEM DESCRIPTION
1.40					1.40		1.40	MILE	614	TEMPORARY CENTER LINE, CLASS I, 621 PAINT
330					330		330	L.F.	614	TEMPORARY CHANNELIZING LINE, CLASS I, 621 PAINT
2					2		2	EACH	614	TEMPORARY LANE ARROW, CLASS I, 621 PAINT
62					62		62	L.F.	614	TEMPORARY STOP LINE, CLASS I, 621 PAINT
1.60					1.60		1.60	MILE	614	TEMPORARY CENTER LINES, CLASS I, 947.03 TYPE C
2.05					2.05		2.05	MILE	614	TEMPORARY CENTER LINES, CLASS II
580					580		580	L.F.	614	TEMPORARY CHANNELIZING LINES, CLASS I, 947.03 TYPE C
1261					1261		1261	L.F.	614	TEMPORARY CHANNELIZING LINES, CLASS II
2.70					2.70		2.70	Mi.	614	TEMPORARY LANE LINES, CLASS II
64					64		64	L.F.	614	TEMPORARY STOP LINES, CLASS I, 947.03 TYPE C
2					2		2	EACH	614	TEMPORARY LANE ARROWS, CLASS I, 947.03 TYPE C
		1261			1261		1261	L.F.	621	CHANNELIZING LINES
		332			332		332	L.F.	621	STOP LINES
		1128			1128		1128	L.F.	621	6" CROSSWALK LINES
		400			400		400	L.F.	621	8" TRANSVERSE LINES
		39			39		39	EACH	621	LANE ARROWS
		9			9		9	EACH	621	WORD "ONLY" ON PAVEMENT, 72"
		2.704			2.70		2.70	MILE	621	LANE LINE
		2.052			2.05		2.05	MILE	621	CENTERLINE
	12		2	4	14	4	18	EACH	625	GROUND ROD
			53	128	53	128	181	L.F.	625	2" CONDUIT 713.04
			58	128	58	128	186	L.F.	625	TRENCH
			5		5		5	L.F.	625	3" CONDUIT 713.04
			3	4	3	4	7	EACH	625	18" PULL BOX, CONCRETE 713.08
		298.75			299		299	S.F.	630	SIGNS, FLAT SHEET
		1			1		1	EACH	630	SPAN WIRE SIGN SUPPORT, TYPE 17.10, DESIGN 4, SPAN 78 FEET
		3			3		3	EACH	630	SPAN WIRE SIGN SUPPORT, TYPE 17.10, DESIGN 4, SPAN 84 FEET
		1			1		1	EACH	630	SPAN WIRE SIGN SUPPORT, TYPE 17.10, DESIGN 5, SPAN 84 FEET
		1			1		1	EACH	630	SPAN WIRE SIGN SUPPORT, TYPE 17.10, DESIGN 7, SPAN 96 FEET
		27.3			27.3		27.3	C.Y.	630	CONCRETE FOR ANCHOR BASE FOUNDATIONS
		7			7		7	EACH	630	SIGN SUPPORT ASSEMBLY, POLE MOUNTED
		984.5			985		985	L.F.	630	GROUND-MOUNTED SUPPORTS, NO. 3 POST
		56			56		56	L.F.	630	GROUND-MOUNTED SUPPORTS, NO. 4 POST
		6			6		6	EACH	630	STREET SIGNS REMOVED AND RESET, AS PER PLAN
		24			24		24	EACH	630	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE
		9			9		9	EACH	630	REMOVAL OF GROUND MOUNTED SIGN AND RE-ERECTION
		18			18		18	EACH	630	REMOVAL OF GROUND MOUNTED POST SUPPORT
		2			2		2	EACH	630	REMOVAL OF OVERHEAD MOUNTED SIGN AND STORAGE
		4			4		4	EACH	630	REMOVAL OF OVERHEAD MOUNTED SIGN AND RE-ERECTION
		4			4		4	EACH	630	REMOVAL OF OVERHEAD MOUNTED SIGN SUPPORT AND STORAGE
		216	56		216	56	272	L.F.	632	LOOP DETECTOR PAVEMENT CUTTING
		676	168		676	168	844	L.F.	632	LOOP DETECTOR WIRE, TYPE "E"
		998	40		998	40	1038	L.F.	632	LOOP DETECTOR LEAD-IN CABLE
		1.98			1.98		1.98	C.Y.	861	CONCRETE FOR CABINET FOUNDATION, AS PER PLAN
		4.8	6.0		4.8	6.0	10.8	C.Y.	632	CONCRETE FOR ANCHOR BASE FOUNDATIONS
		2			2		2	EACH	632	STRAIN POLE, TYPE TC-81.10, DESIGN 6, 30 FEET
			2			2	2	EACH	632	STRAIN POLE, TYPE TC-81.10, DESIGN 7, 30 FEET
			2			2	2	EACH	632	PEDESTAL, 8 FEET
		2	2		2	2	4	EACH	632	CABLE SUPPORT ASSEMBLY
			2			2	2	EACH	632	CONNECTION TO EXISTING CONDUIT
		288			288		288	L.F.	632	MESSENGER WIRE, 7 STRAND, 3/8" DIA. WITH ACCESSORIES
			125			125	125	L.F.	632	MESSENGER WIRE, 7 STRAND, 7/16" DIA. WITH ACCESSORIES
		32			32		32	L.F.	632	SIGNAL CABLE, 2/C NO. 14 AWG
		423	224		423	224	647	L.F.	632	SIGNAL CABLE, 5/C NO. 14 AWG
		322			322		322	L.F.	632	SIGNAL CABLE, 7/C NO. 14 AWG
			165			165	165	L.F.	632	SIGNAL CABLE, 9/C NO. 14 AWG
		453			453		453	L.F.	632	SIGNAL CABLE, 12/C NO. 14 AWG
		1	1		2		2	EACH	632	REMOVAL OF TRAFFIC SIGNAL INSTALLATION
		6	6		6	6	12	EACH	632	RE-USE OF VEHICULAR SIGNAL HEAD
		4	4		4	4	8	EACH	632	RE-USE OF PEDESTRIAN SIGNAL HEAD
		4	4		4	4	8	EACH	632	RE-USE OF PEDESTRIAN PUSH BUTTON
		1	1		1	1	2	EACH	632	POWER SERVICE <i>as per plan</i>
		60	25		60	25	85	L.F.	632	POWER CABLE, 3/C NO. 8 AWG
		LUMP			LUMP		LUMP	LUMP	632	RE-CONNECTING TELEPHONE INTERCONNECT
		1	1		1	1	2	EACH	632	CONDUIT RISER, 2" DIA.
		1			1		1	EACH	861	RE-USE OF CONTROLLER AND CABINET

CALC:	P.C.B.	4-83
CHK:	R.G.	4-83

BRUNING 44-132-30645-1