

FHWA REGION	STATE	PROJECT	
5	OHIO		

82
114

LAKE COUNTY
LAK-20-6.65

2
13

GENERAL NOTES

TRAFFIC CONTROL NOTES

ITEM 632 POWER SERVICE, AS PER PLAN

ELECTRIC POWER SHALL BE OBTAINED FROM THE CLEVELAND ELECTRIC ILLUMINATING CO., 55 PUBLIC SQUARE, ROOM 491, CLEVELAND, OHIO 44101 AT THE LOCATION INDICATED ON THE PLANS. POWER SUPPLIED SHALL BE 120 VOLTS. THE METER BASE IS TO BE OMITTED FROM THIS ITEM.

ITEM 632 RE-CONNECTING TELEPHONE INTERCONNECT, AS PER PLAN

THIS ITEM SHALL INCLUDE FURNISHING AND INSTALLING THE TELEPHONE INTERCONNECT CABLE FROM THE RELOCATED POWER SERVICE POLE TO THE RELOCATED TRAFFIC CONTROLLER. THIS WORK WILL BE COORDINATED WITH CLEVELAND ELECTRIC ILLUMINATING CO. AND OHIO BELL TELEPHONE COMPANY.

ITEM 861 RE-USE OF CONTROLLER AND CABINET

THIS ITEM SHALL CONSIST OF REMOVING AND INSTALLING THE EXISTING CONTROLLER AND CABINET COMPLETELY WIRED AND IN GOOD WORKING CONDITION.

ITEM 861 CONCRETE FOR CABINET FOUNDATION, as per plan

THIS ITEM SHALL INCLUDE FURNISHING AND INSTALLING THE CONDUIT ELLS AND ANCHOR BOLTS.

ITEM 630 GROUND MOUNTED STREET SIGNS REMOVED AND RESET, AS PER PLAN

THIS ITEM SHALL CONSIST OF REMOVING AND CLEANING THE EXISTING STREET SIGNS INCLUDING SUPPORTS, IF APPLICABLE, AND RE-SETTING THEM AT LOCATIONS SHOWN ON THE PLANS. THE SUPPORTS SHALL BE RE-SET TO THE SAME DEPTH AS EXISTING. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE INCURRED TO THE SIGNS AND SUPPORTS DUE TO HIS NEGLIGENCE AND SHALL REPLACE THEM AT HIS EXPENSE. ALL UNSALVABLE MATERIAL WILL BE PROVIDED BY THE CITY OF MENTOR TO BE RE-SET BY THE CONTRACTOR, AT THE DIRECTION OF THE ENGINEERS.

STORAGE OF SIGNS AND SUPPORTS

ALL SIGNS AND SUPPORTS REMOVED FOR STORAGE SHALL BE STORED ON THE PROJECT SITE FOR SALVAGE BY THE CITY OF MENTOR. THE CONTRACTOR SHALL NOTIFY THE CITY OF MENTOR WHEN THE ITEMS ARE REMOVED.

CITY OF MENTOR
8500 CIVIC CENTER BLVD.,
MENTOR, OHIO 44060
PHONE: (216) 255-1100

REMOVAL OF TRAFFIC SIGNAL INSTALLATION

THE TWO EXISTING STRAIN POLES TO BE REMOVED AT STATE ROUTE 306 AND AT MIDDLESEX SHALL BE STORED ON THE PROJECT SITE FOR SALVAGE BY THE CITY OF MENTOR. THE CONTRACTOR SHALL NOTIFY THE CITY OF MENTOR AFTER THEIR REMOVAL FROM THE INTERSECTION.

TRAFFIC CONTROL STANDARD CONSTRUCTION DRAWING AND SPECIFICATIONS

REFERENCE TO SUPPLEMENTAL SPECIFICATIONS 857, 858, 859, 957, 958 AND 959 ON THE TRAFFIC CONTROL STANDARD CONSTRUCTION DRAWINGS IN THESE PLANS SHALL BE CONSIDERED TO READ AS RESPECTIVE REFERENCES TO ITEMS 630, 631, 632, 730, 731 AND 732.

614 TEMPORARY MAINTENANCE OF EXISTING SIGNALS

INCIDENTAL TO THE REQUIREMENTS FOR MAINTAINING TRAFFIC IN ACCORDANCE WITH 614.03, EXISTING TRAFFIC SIGNALS AT THE INTERSECTIONS OF U.S. ROUTE 20 AND STATE ROUTE 306; MIDDLESEX SHALL BE TEMPORARILY MAINTAINED UNTIL THE NEW TRAFFIC SIGNAL INSTALLATION IS IN OPERATION.

ANY COSTS FOR THE TEMPORARY MAINTENANCE OF EXISTING SIGNALS SHALL BE INCLUDED IN THE LUMP SUM BID FOR 614 MAINTAINING TRAFFIC.

CONNECTION TO EXISTING CONDUIT

THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING THE EXISTING 2" CONDUIT UNDER MIDDLESEX ROAD, AND MAKING THE NECESSARY CONNECTIONS TO EXTEND IT INTO THE PROPOSED PULLBOX AND STRAIN POLE FOUNDATION AT EACH END.

THE COST OF THIS WORK SHALL BE INCLUDED UNDER BID ITEM 632 CONNECTIONS TO EXISTING CONDUIT.