SUB-SUMMARY — TRAFFIC CONTROL

CALC: PCB 12-82
CHK: RG 12-82

FHWA REGION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY
LAK-20-6.65

86/114

6/13

FROM SHEET No.	SIGN SUPPORT No.	SIGN LOCATION	SIGN DESIGNATION	EFFECTIVE SIGN SIZE "He"	SIGN AND SUPPORT QUANTITIES ITEM 630: SIGNS FLAT SHEET (S.F.)	SPAN WIRE SIGN SUPPORT 17.10 DESIGN 4 SPAN 78' (EA.)	SPAN WIRE SIGN SUPPORT 17.10 DESIGN 4 SPAN 84' (EA.)	SPAN WIRE SIGN SUPPORT 17.10 DESIGN 5 SPAN 84' (EA.)	SPAN WIRE SIGN SUPPORT 17.10 DESIGN 7 SPAN 96' (EA.)	CONCRETE FOR ANCHOR BASE FOUND. (C.Y.)	SIGN SUPPORT ASSEM. POLE MOUNTED (EA.)	STRUCTURAL SUPPORTS: GROUND MOUNTED SUPPORT NO. 3 POST (L.F. LT. / CTR. / RT.)	STRUCTURAL SUPPORTS: GROUND MOUNTED SUPPORT NO. 4 POST (L.F. LT. / CTR. / RT.)	REMOVALS ITEM 630: REMOVAL OF GROUND MOUNTED SIGN AND STORAGE (EA.)	REMOVAL OF GROUND MOUNTED SIGN AND RE-ERECTION (EA.)	REMOVAL OF OVERHEAD MOUNTED SIGN AND STORAGE (EA.)	REMOVAL OF OVERHEAD MOUNTED SIGN AND RE-ERECTION (EA.)	REMOVAL OF GROUND MOUNTED POST SUPPORT (EA.)	REM. OF OVERHEAD SIGN SUPP. & STORAGE (EA.)	STREET SIGNS REMOVED AND RESET, AS PER PLAN (EA.)	ELECTRICAL QUANTITIES ITEM 625: GROUND RODS (EA.)
		U.S. 20																			
		100+20	L+R	30"x36"	7.5		1			4.3											2
				30"x36"	7.5																
		100+20	LT.	24"x30"	5.0						1										
		100+68	LT.											1					1		
		101+88 TO 102+70	RT.																	1	
		108+22 TO 108+65	RT.																	1	
		110+40	L+R	30"x36"	7.5		1			4.3											2
				30"x36"	7.5																
		113+02	RT.										13.0			1			1		
		117+40	LT.	24"x30"	5.0						1										
		117+28	LT.											1					1		
		117+40	L+R	30"x42"	8.75	1				4.3											2
				30"x42"	8.75																
		MIDLAND																			
		9+39	RT.										13.0			1			1		
		S.R. 306																			
		9+41 TO 9+37	RT.										13.0			1			1		
		DARTMOOR																			
		9+42	RT.										13.0			1			1		
		90+60 (U.S.20)	RT.																	1	
		STOCKBRIDGE																			
		9+41	RT.										13.0			1			1		
		BRENTWOOD																			
		9+49	RT.										13.0			1			1		
		46+00 - 118+00	L+R	12"x18" ("72" NO PARKING" SIGNS + SUPPORTS) = 108.0						(12x70) = 840											
		SUB-TOTAL FROM SUB-SUMMARY			133.25		1	1		1	14.4	5		66.5	56		22	3	2	4	10	4	3		6
		TOTALS (TO GENERAL SUMMARY)			298.75	1	3	1		1	27.3	7		984.5	56		24	9	2	4	18	4	6		12