621 - PAVEMENT MARKING

FHWA REGION	STATE	PROJECT	
5	OHIO		

87 / 114

7 / 13

LAKE COUNTY
LAK-20-G.05

CALC: PCB 12-82
CHK: RG 12-82

RAMP OR ROADWAY	LENGTH	STATION	TO STATION		4" LANE LINES	4" CENTER LINES SOLID-DOUBLE	4" CENTER LINES BROKEN & SOLID-DOUBLE		8" CHANNELIZING LINES	24" STOP LINES	6" CROSSWALK LINES		8" TRANSVERSE LINES (YELLOW)		LANE ARROWS	WORD ON PAVEMENT "ONLY" 72" INL.
	L.F.				L.F.	L.F.	L.F.		L.F.	L.F.	L.F.		L.F.		EACH	EACH
U.S.R. 20																
	2678	44+32	71+10		5356	2678										
	125	71+10	72+35		125											
	15	72+35	72+50		30	15										
	480	72+50	77+30		960	960							400			
	220	77+30	79+50		446	220			220							
		78+20													1	
		78+90														2
		79+30													3	
		79+52								39						
		79+56									68					
		79+62									72					
		80+58	80+84								74					
		80+65	80+90								71					
		80+88	80+94							39						
	250	80+90	83+40		500	290			413							
		81+13													3	
		81+53														3
		81+73													1	
		82+13														1
		82+33													1	
	620	83+40	89+60		1240		1240		200							
		83+13													1	
		84+16													2	
		84+53													1	
		88+26													2	
	115	89+60	90+75		115											
	395	90+75	94+70		790		790									
		91+08													2	
		94+36													2	
	120	94+70	95+90		120											
	570	95+90	101+60		1146		1140									
		96+29													2	
		101+21													2	
		101+62								38						
		101+64									64					
		101+72									65					
			TOTALS		10828	4163	3170		833	116	414		400		23	6

RAMP OR ROADWAY	LENGTH	STATION	TO STATION		4" LANE LINES	4" CENTER LINES SOLID-DOUBLE	4" CENTER LINES BROKEN & SOLID-DOUBLE		8" CHANNELIZING LINES	24" STOP LINES	6" CROSSWALK LINES		8" TRANSVERSE LINES (YELLOW)		LANE ARROWS	WORD ON PAVEMENT "ONLY" 72" INL.
	L.F.				L.F.	L.F.	L.F.		L.F.	L.F.	L.F.		L.F.		EACH	EACH
U.S.R. 20		TOTALS FROM LEFT			10828	4163	3170		833	116	414		400		23	6
		102+83								38						
	456	102+85	107+40		910		910									
		103+36													2	
		106+64													2	
	120	107+40	108+60		120											
	1040	108+60	119+00		2080	80	2000									
		108+88													2	
		113+80													2	
		117+08													2	
	170	119+00	120+70		340	170			340							
		119+30													2	
		120+10														2
		120+50													2	
		120+72								54						
MIDLAND		8+93	9+41			50				14						
		9+43	9+47								37					
		9+49	9+53								43					
S.R. 306		8+50	9+40			88			88							
		8+85														1
		9+25													2	
		9+40								27						
		9+42	9+46								62					
		9+48	9+53								76					
DARTMOOR		8+94	9+42			50				20						
		9+46									52					
		9+52									62					
STOCKBRIDGE		8+91	9+43			50				16						
		9+43	9+48								59					
		9+45	9+54								76					
MIDDLESEX		8+93	9+45			50				21						
		9+49									51					
		9+55									64					
BRENTWOOD		8+93	9+45			50				26						
		9+45	9+50								57					
		9+52	9+58								75					
TOTALS (TO GENERAL SUMMARY)				FEET	14278	4751	6080		1261	332	1128		400		39	9
				MILES	2.704	0.900	1.152		TOTAL CENTERLINE TO GENERAL SUMMARY =						(1.152	+ 0.900) = 2.052

620 - DELINEATORS

PARTICIPATION	RAMP OR ROADWAY	STATION	TO STATION		SIDE	INTERNAL	TYPE A POST	TYPE A BRACKET	TYPE D POST	TYPE D BRACKET

SUB-SUMMARIES - PAVEMENT MARKING & DELINEATORS

BRUNING 44-132 30845-1