GENERAL SUMMARY

LAKE COUNTY
LAK-283-0.000

metric units

121
121

PLAN NO.

ITEM	SHEET NUMBER 11	12	13							94			117		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION
																			SANITARY SEWER	
604	12												9		604	M34501	21	EA.	MANHOLE ADJUSTED TO GRADE, AS PER PLAN (SANITARY)	11
604		4													604	M35501	4	EA.	MANHOLE RECONSTRUCTED TO GRADE, AS PER PLAN (SANITARY)	12
																			TRAFFIC CONTROL	
632			24												632	M26500	24	EA.	DETECTOR LOOP	
642										2.64					642	M00102	2.64	KM.	EDGE LINE, TYPE 2	
642										4.64					642	M00202	4.64	KM.	LANE LINE, TYPE 2	
642										1.97					642	M00302	1.97	KM.	CENTERLINE, TYPE 2 (DOUBLE SOLID)	
642										4.62					642	M00302	4.62	KM.	CENTERLINE, TYPE 2 (SOLID / DASHED)	
642										582					642	M00402	582	M.	CHANNELIZING LINE, TYPE 2	
642										378					642	M00502	378	M.	STOP LINES, TYPE 2	
642										1608					642	M00602	1608	M.	CROSSWALK LINES, TYPE 2	
642										70					642	M00702	70	M.	TRANSVERSE LINE, TYPE 2	
642										73					642	M01302	73	EA.	LANE ARROWS, TYPE 2	
642										42					642	M01402	42	EA.	WORD ON PAVEMENT, 1800mm, TYPE 2, (ONLY)	
																			MAINTENANCE OF TRAFFIC	
614			315												614	M13000	315	C. M.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
614			14.4												614	M20500	14.4	KM.	TEMPORARY LANE LINES, CLASS II, 642 PAINT	
614			20.1												614	M21500	20.1	KM.	TEMPORARY CENTERLINE, CLASS II, 642 PAINT	
614			1122												614	M26200	1122	M.	TEMPORARY STOP LINE, CLASS I, 642 PAINT	
614															614	M11000	LUMP		MAINTAINING TRAFFIC	
619															619	M16010	13	MNTH	FIELD OFFICE, TYPE B	
SPEC															SPEC	619M26010	13	MNTH	COMPUTER EQUIPMENT FOR TYPE B OR C OFFICE	
623															623	M10000	LUMP		CONSTRUCTION LAYOUT STAKES	
624															624	M10000	LUMP		MOBILIZATION	

GENSUM - LAYER 53