

SIGN QUANTITIES

CALC BY	LMI	CALC BY	CDB
DATE	6/93	DATE	3/92
CHKD BY	SJS	CHKD BY	MJN
DATE	6/93	DATE	7/92
REVISED			

LAK-283-3.83
PLAN 81

OHIO
FHWA
REGION 5

77
79

TRAFFIC SIGNS AND POSTS

SHT. NO.	SIGN LOCATION PROP. LOCATION (EXIST. LOCATION)	REFERENCE TO SR 283	SIGN CODE NO.	ITEM 630						
				SIGN FLAT SHEET	GROUND MOUNTED SUPPORT, NO. 3 POST	STREET NAME SIGN SUPPORT	REMOVAL OF GROUND MOUNTED SIGN & REERECTION	REMOVAL OF GROUND MOUNTED SIGN & STORAGE	REMOVAL OF GROUND MOUNTED POST SUPPORT & DISPOSAL	
				SQ.FT.	LIN.FT.	EACH	EACH	EACH	EACH	
72	SR 91, WEST SIDE, 750' FROM SR 283	SOUTH*	W-76B-30	6.25	13.5					
72	STA 124+30 (125+60)	37' RT	W-76B-30		13.5		1			1
72	STA 125+10	40' RT	BM-29	0.75	12.0					
			BM-24(R)					1		1
72	STA 125+65 (125+60)	61' RT	R-1-30		12.0		1			
72	STA 125+80 (125+55)	62' RT	R5-3		13.0		1			1
			R-1(SPEC)				1			
72	STA 125+81	42' RT	M-2-24-2		13.5		1			1
			M-24(L)				1			
72	STA 126+00	60' RT	R9-5	1.50	12.0					
72	STA 127+05	100' RT	M-13A-24	1.00	13.0					
			M-7-24	3.00						
			BM-25	0.75						
72	STA 127+10	55' RT	R-72E-18	2.25	13.0					
			R-72F(R)-18	1.50						
72	STA 127+10	22' LT	R-72E-18	2.25	13.0					
			R-72F(L)-18	1.50						
72	STA 128+00	21' LT	R-149-24	5.00	12.0					
72	STA 129+00	33' RT	R-151-24	5.00	12.0					
72	STA 129+85	21' LT	R-88-24		14.0		1			1
			R-55-12	1.50				1		
72	STA 133+90 (133+23)	21' LT	R-10-24		13.5		1			1
			R-55-12	1.50				1		
72	STA 135+00	22' RT	EL-SPEC1		24.0					2
72	STA 135+00	21' LT	R-151-24	5.00	12.0					
72	STA 141+50	33' LT	R-151-24	5.00	12.0					
72	ERIE RD, WEST SIDE, 250' FROM SR 283	NORTH**	W-76B-30	6.25	13.5					
72	ERIE RD, EAST SIDE, 250' FROM SR 283	SOUTH**	W-76B-30	6.25	13.5					
72	STA 144+88	23' RT	R-151-24	5.00	12.0					
72	STA 154+00	21' RT	R-151-24	5.00	12.0					
72	STA 161+50	22' LT	R-151-24	5.00	12.0					
72	STA 163+45	22' RT	W-1(SP-1)	6.25	14.0					
			W-51-18	2.25						
72	STA 167+75	20' LT	W-1(SP-2)	6.25	14.0					
			W-51-18	2.25						

TRAFFIC SIGNS AND POSTS

SHT. NO.	SIGN LOCATION PROP. LOCATION (EXIST. LOCATION)	REFERENCE TO SR 283	SIGN CODE NO.	ITEM 630						
				SIGN FLAT SHEET	GROUND MOUNTED SUPPORT, NO. 3 POST	STREET NAME SIGN SUPPORT	REMOVAL OF GROUND MOUNTED SIGN & REERECTION	REMOVAL OF GROUND MOUNTED SIGN & STORAGE	REMOVAL OF GROUND MOUNTED POST SUPPORT & DISPOSAL	
				SQ.FT.	LIN.FT.	EACH	EACH	EACH	EACH	
72	STA 169+80	60' RT	W-76B-30	6.25	13.5					
72	STA 170+10	20' RT	R-151-24	5.00	12.0					
72	STA 172+65	16' RT	EL-SPEC2	5.00	12.0				1	1
73	STA 176+40	25' LT	EL-SPEC2	5.00	12.0				1	1
73	STA 178+00	26' LT	W-1(SP-2)	6.25	14.0					
			W-51-18	2.25						
73	STA 180+50	36' RT	R4-4-36	7.50	27.0					
73	STA 182+60	35' RT	R-32R-30	6.25	13.5					
73	STA 184+00	40' RT	D-14-8		13.5	1	2			1
73	REEVES RD, NORTH SIDE, 250' FROM SR 283	EAST*	W-76B-30	6.25	13.5					
73	STA 186+00	24' RT	R-151-24	5.00	12.0					
73	STA 186+55	24' RT	EL-SPEC3		12.0			1		1
73	STA 195+55	19' RT	R-21-24		13.0			1		1
73	STA 196+00	23' LT	R-151-24	5.00	12.0					
73	STA 198+90	24' LT	W-82-30		14.0			1		1
			WP-82-24					1		
73	STA 200+00	20' RT	R-151-24	5.00	12.0					
73	STA 214+00	20' LT	R-151-24	5.00	12.0					
73	STA 218+10	30' LT	D-14-8		13.5	1	2			1
73	STA 218+50	22' RT	R-151-24	5.00	12.0					
73	STA 223+75	22' LT	R-151-24	5.00	12.0					
73	STA 224+04	42' RT	D-14-8		13.5	1	2			1
73	STA 224+18	43' LT	R-1-30		13.0			1		1
73	STA 224+55	54' RT	R-1-30		13.0			1		1
73	STA 224+69	31' LT	D-14-8		13.5	1	2			1
73	STA 230+00	21' RT	R-151-24	5.00	12.0					
73	STA 239+50	49' RT	D-14-8		13.5	1	1			1
73	STA 245+25	21' RT	R-151-24	5.00	12.0					
73	STA 250+25	20' LT	R-151-24	5.00	12.0					
73	STA 260+20	21' RT	R-151-24	5.00	12.0					
73	STA 281+00	21' RT	R-149-24	5.00	12.0					
73	STA 283+40	21' LT	M-13A-24	1.00	13.0					
			R-151-24	5.00						
73	STA 283+60	21' LT	EL-SPEC4		13.0			1		1
	TOTAL			199.00	727.0	5	24	5		21