



PLAN NO.
BR-20-86

UTILITY OWNERSHIP

THE FOLLOWING UTILITIES AND OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT:

THE CLEVELAND ELECTRIC
ILLUMINATING COMPANY
55 PUBLIC SQUARE
CLEVELAND, OHIO 44101
(216) 622-9800

OHIO WATER SERVICE
7473 CENTER STREET
MENTOR, OHIO 44060
(216) 255-3421

OHIO BELL TELEPHONE CO.
820 WEST SUPERIOR AVE.
CLEVELAND, OHIO 44113
(216) 822-6241

THE EAST OHIO GAS COMPANY
1201 EAST 55TH STREET
CLEVELAND, OHIO 44103
(216) 432-6803

UTILITIES NOTIFICATION

THE CONTRACTOR'S ATTENTION SHALL BE DIRECTED TO SECTION 105.06 OF THE CMS

THE LOCATIONS OF UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS OF THE UTILITY AS REQUIRED BY ORC. 153.64.

ITEM 404 - BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC

THIS ITEM SHALL BE USED TO REPAIR HOLES IN THE BRIDGE DECK, ROADWAY SURFACE, AND BERMS WHICH ARE DAMAGED DURING THE CLOSURE. THE CONTRACTOR SHALL USE THIS ITEM TO MAINTAIN THE HIGHWAY ACCORDING TO SEC. 614.02. THE CONTRACTOR SHALL PERFORM THE ABOVE WORK DURING THE HOURS AS PER THE MAINTENANCE OF TRAFFIC PLANS. THE FOLLOWING ESTIMATED QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR THE MAINTENANCE OF TRAFFIC TO BE USED AS DIRECTED BY THE ENGINEER.

ITEM 404 - BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC 2 CU. YDS.

ITEM 407 - TACK COAT

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER ON THE APPROACH SLABS AND APPROACH PAVEMENT FEATHERS.

ITEM 407 - TACK COAT 32 GALLONS

ITEM 509 - REINFORCING STEEL, AS PER PLAN

THIS ITEM SHALL BE USED TO REPLACE REINFORCING STEEL WHICH IS BENT, ELONGATED, MISSING, OR EXTREMELY CORRODED. BAR SHALL BE THE SAME SIZE AS THE ORIGINAL BARS AND SHALL BE PLACED AS NEAR AS POSSIBLE TO THEIR ORIGINAL LOCATION. BARS SHALL BE LAPPED ACCORDING TO SEC. 509.08. PAYMENT FOR THIS ITEM SHALL INCLUDE THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLETE THE ABOVE WORK, INCLUDING REMOVAL OF THE EXISTING STEEL.

THE FOLLOWING ESTIMATED QUANTITY OF REINFORCING STEEL IS TO BE USED WHERE AND AS DIRECTED BY THE ENGINEER.

ITEM 509 - REINFORCING STEEL, AS PER PLAN 200 POUNDS

ITEM 606 - GUARDRAIL, TYPE 5

THE FOLLOWING QUANTITY HAS BEEN INCLUDED IN THE ESTIMATED QUANTITIES TO BE USED AS DIRECTED BY THE ENGINEER TO TAPER THE PROPOSED BRIDGE TERMINAL ASSEMBLIES TO THE EXISTING GUARDRAIL.

ITEM 606 - GUARDRAIL, TYPE 5 50 LIN. FT.

GENERAL NOTES