

# GENERAL SUMMARY

ITEM	SHEET NUMBER																				ITEM	TOTAL	UNIT	DESCRIPTION			
	4	5	8	9	10	11	12	13	14	15	16	17	41	44	45												
																											<i>Roadway</i>
202					273	134	470		40												202	917	Lin.Ft.	Guardrail Removed			
201																					201	Lump		Clearing And Grubbing			
202					5	40		110	8	90											202	253	Lin.Ft.	Pipe Removed, 24" And Under			
202					48					70											202	118	Sq.Yd.	Pavement Removed			
202						Lump															202	Lump		Structures Removed			
202					1	1			1												202	3	Ea.	Catch Basin Removed			
203					135	516		67	366	736	106										203	2024	Cu.Yd.	Excavation Not Including Embankment Construction			
203					13	1394	244	25	122	156	18										203	1972	Cu.Yd.	Embankment			
203		4256																			203	4256	Sq.Yd.	Subgrade Compaction			
404																					404	50	Cu.Yd.	Bituminous Concrete For Maintaining Traffic			
410																					410	50	Cu.Yd.	Traffic Compacted Surface, Type A01 B			
410																					410	50	Cu.Yd.	Traffic Compacted Surface, Type C			
604					1	2	1														604	4	Ea.	Monument Assembly, Standard			
604									2												604	2	Ea.	Monument Box, Adjusted To Grade			
606					570	172.5	220		62.5												606	1025	Lin.Ft.	Guardrail, Type 5			
606						1															606	1	Ea.	Anchor Assembly, Standard Type T			
606					3	3	2		1												606	9	Ea.	Anchor Assembly, Standard Type A			
615																					615	1000	Sq.Yd.	Temporary Pavement, Class B			
616																					616	10	M.Gal.	Water			
616																					616	50	Ton	Calcium Chloride			
622																					622	720	Lin.Ft.	Temporary Concrete Barriers			
																					615	Lump		Temporary Roads			
202																					202	134	Sq.Yd.	Wearing Course Removed			
																								<i>Erosion Control</i>			
207		56																			207	56	Ea.	Straw Or Hay Bales			
207		1435																			207	1435	Sq.Yd.	Temporary Seeding And Mulching			
207		20																			207	20	Lin.Ft.	Temporary Slope Drains			
207		100																			207	100	Cu.Yd.	Temporary Benches, Dikes, Dams & Sediment Basins			
207		100																			207	100	Lin.Ft.	Filter Fabric Fence			
601		4																			601	4	Cu.Yd.	Rock Channel Protection, Type C, Without Filter			
659		3																			659	3	M.Gal.	Water			
659					449	17	1			146	275										659	7178	Sq.Yd.	Seeding And Mulching			
659		0.1	0.65																		659	0.75	Ton	Commercial Fertilizer			
659			3																		659	3.3	Ton	Agricultural Liming			
659		360																			659	360	Sq.Yd.	Repair Seeding And Mulching			
659		16																			659	16	M.Sq.Ft.	Mowing			
																								<i>Drainage</i>			
603						148			62	226											603	434	Lin.Ft.	12" Conduit, Type B, 706.01, 706.02 or 706.08			
603					15	16		120	58	100											603	309	Lin.Ft.	12" Conduit, Type C, 706.01, 706.02 or 706.08			
603										20											603	20	Lin.Ft.	12" Conduit, Type D, 707.01 Or 707.02			
603		100				38															603	138	Lin.Ft.	6" Conduit, Type B, 706.01, 706.02 or 706.08 with joints, as per 706.11 or 706.12			
603		100																			603	100	Lin.Ft.	6" Conduit, Type C, 706.01, 706.02, 706.08 with joints as per 706.11 or 706.12			
603		100																			603	100	Lin.Ft.	6" Conduit, Type E, 706.01, 706.02 or 706.08			
603		100			12	15			10	46											603	182	Lin.Ft.	6" Conduit, Type F			