NOTE: ANY ITEM 310 IN THE PLANS SHALL BE CONSIDERED AS ITEM 304, AGGREGATE BASE, AS PER PLAN.
ALL ITEMS 402, 403, OR 404 IN THE PLANS SHALL BE CONSIDERED AS ITEMS 448 (402: 44846050, 403: 44847020, 404: 44848020)

GENERAL SUMMARY

CALC. BY J.J.C. DATE 7-94	LAK - 283 - 6.79	OHIO	10/58
CHKD. BY C.C.H. DATE 7-94		FHWA REGION 5	

ITEM	SHEET NUMBER 4	5	7	13	14	15	16	17	18	19	20	21	22	23	24	25	26	53	ITEM	ITEM EXT.	QUANTITY	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION
																							ROADWAY	
201																			201	11000	LUMP		CLEARING AND GRUBBING	
202					132													530	202	23000	662	SQ.YD.	PAVEMENT REMOVED	
202	3760						122	135	336					280	52	221	44		202	30000	4950	SQ.FT.	WALK REMOVED	
203		100		180	219	222	172	156	178	38	111	224	182	160	147	190	85	163	203	12000	2528	CU.YD.	EXCAVATION, NOT INCLUDING EMBANKMENT CONSTRUCTION	
203				463	600	600	459	420	455	100	300	600	466	410	434	499	230		203	50000	6036	SQ.YD.	SUBGRADE COMPACTION	
203	49																		203	60001	49	STATION	LINEAR GRADING, AS PER PLAN	4
608	3760						163	145	294					287	61	225	37		608	10000	4972	SQ.FT.	4" CONCRETE WALK	
608	12						4	4	8					8	2				608	54000	38	EACH	CURB RAMP, TYPE 2	
616			100																616	10000	100	M-GAL.	WATER	
616			10																616	20000	10	TON	CALCIUM CHLORIDE	
																							EROSION CONTROL	
207		1600																	207	10000	1600	SQ.YD.	TEMPORARY SEEDING AND MULCHING	
207		500																	207	30000	500	LIN.FT.	FILTER FABRIC FENCE	
207		500																	207	70000	500	EACH	STRAW OR HAY BALES	
659		0.53																	659	20000	0.53	TON	COMMERCIAL FERTILIZER	
659		2.32																	659	30000	2.32	TON	AGRICULTURAL LIMING	
659		15																	659	35000	15	M-GAL.	WATER	
660		5100																	660	30000	5100	SQ.YD.	SODDING	
																							PAVEMENT	
251		1340																	251	01000	1340	SQ.YD.	PARTIAL DEPTH PAVEMENT REPAIR	
252		1200																	252	01000	1200	SQ.YD.	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE PELACEMENT	
252		3600																	252	01500	3600	LIN. FT.	FULL DEPTH PAVEMENT SAWING	
253		150			40	40	18					20				47			253	01000	315	SQ.YD.	PAVEMENT REPAIR	
254				849	1100	1100	1202	984	1285	183	550	1100	856	1371	956	1452	404		254	01000	13,392	SQ.YD.	PAVEMENT PLANING, BITUMINOUS	
301				90.1	116.8	116.6	89.3	81.7	88.5	19.4	58.4	116.6	90.8	79.9	84.6	97.0	44.7		301	46000	1175	CU.YD.	BITUMINOUS AGGREGATE BASE, PG 64-22	
304		100		51.4	75.6	66.6	51.0	46.7	50.5	11.2	33.4	66.6	51.8	45.5	48.3	55.4	25.5	120	304	20001	900	CU.YD.	AGGREGATE BASE, AS PER PLAN	5
448				22.5	29.2	31.2	22.3	20.4	22.0	4.8	14.6	29.2	22.6	20.0	21.1	24.2	11.2	14	448	46050	310	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 2, PG 64-22	
448				11.8	15.3	15.3	16.7	13.7	17.8	2.5	7.6	15.3	11.9	19.0	13.3	20.2	5.6		448	46020	186	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22	
448				45.6	60.4	59.0	57.7	48.8	60.4	9.8	29.5	59.0	45.9	61.9	48.3	67.7	22.0		448	47020	676	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	
448																		29	448	48020	29	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22(DRIVEWAYS)	
407				132	174	170	166	140	174	28	85	170	132	178	139	195	253		407	10000	2136	GAL.	TACK COAT	
408																		247	408	10000	247	GAL.	BITUMINOUS PRIME COAT	
411				20.2	25.3	26.9	17.9	9.8	9.6	2.4	15.4	31.0	23.3	20.2	16.2	26.8	10.4		411	10000	256	CU.YD.	STABILIZED CRUSHED AGGREGATE	
452																		216	452	10000	216	SQ.YD.	6" PLAIN CONCRETE PAVEMENT	
452																		151	452	12000	151	SQ.YD.	8" PLAIN CONCRETE PAVEMENT	
452					107														452	13000	107	SQ.YD.	9" PLAIN CONCRETE PAVEMENT	
609					65														609	14000	65	LIN.FT.	CURB, TYPE 2-A	

\32479\GENSUM1.DWG PLT:1=20