

GENERAL SUMMARY

Item	ROADWAY		
E-1	Roadway Excavation (Unclassified)	43169	Cu. Yds.
E-4	Borrow (Contractor to furnish)	17707	Cu. Yds.
E-5	Finishing Shoulders, Slopes, Ditches (both sides)	20022.55	Lin. Ft.
I-3	6" V.S.P.(a) Roadway Drainage	38	Lin. Ft.
I-3	12" V.S.P.(a) Roadway Drainage	408	Lin. Ft.
I-3	15" V.S.P.(a) Roadway Drainage	1091	Lin. Ft.
I-3	18" V.S.P.(a) Roadway Drainage	542	Lin. Ft.
I-4	6" drain tile, 30" deep, cinder backfill in place	2000	Lin. Ft.
I-6	Pipe removed	284	Lin. Ft.
S-1	Concrete 1:5 1/2 mix (headwalls)	0.60	Cu. Yds.
I-1	12" Corr. iron pipe (Drives)	260	Lin. Ft.
I-1	15" " " " "	40	Lin. Ft.
I-1	30" " " " "	20	Lin. Ft.
I-17	Aggregate, drives & road approaches in place	248	Cu. Yds.
I-8	Standard Inlet Basins (I-8-C.B.#1-2)	2	Units
I-8	Inlet Basins (I-8-I#5)	1	Unit
I-8	Manholes (I-8-M.H.#1)	1	Unit
E-8	Concrete Gutter Curb Removed	95	Lin. Ft.
E-9	Trees removed (over 8" dia)	56	Units
I-15	Guard Rail (I-15-S.C.)	2944	Lin. Ft.
I-14	Concrete Gutter (I-14-G#1)	980	Lin. Ft.
I-14	Concrete Gutter (I-14-G#2)	2410	Lin. Ft.
I-14	Concrete Circular Outlet (I-14-G#3)	447	Lin. Ft.
E-8	Removal & disposal of existing 6" conc. pav.	2000	Sq. Yds.

PAVEMENT

T-71	Reinforced Concrete Pavement	37090.48	Sq. Yds.
T-71	Reinforced Concrete Pavement (resurfacing)	188245	Cu. Yds.
I-12	Combined Concrete Curb & Gutter (I-12-C.C.Type 2)	420	Lin. Ft.

STRUCTURES 20' SPAN and UNDER

Item			
E-2	Structural Excavation (Unclassified)	343	Cu. Yds.
S-1	Concrete (1:5 1/2 Mix)	2415	Cu. Yds.
S-1	Concrete (1:6 1/2 Mix)	54	Cu. Yds.
S-4	Reinforcing Steel	637	Lbs.
S-22	Removal of Existing Stone Masonry	44	Cu. Yds.
S-22	Removal of Existing Concrete Masonry	95	Cu. Yds.
S-27	12" V.S.P.(enc.)	192	Lin. Ft.
S-27	15" V.S.P.(enc.)	204	Lin. Ft.
S-27	18" V.S.P.(enc.)	56	Lin. Ft.
S-27	12" Cast Iron Pipe	198	Lin. Ft.
S-27	16" Cast Iron Pipe	538	Lin. Ft.
S-27	18" Cast Iron Pipe	15	Lin. Ft.
S-27	24" Cast Iron Pipe	50	Lin. Ft.
I-4	12" V.S.P.(a)	20	Lin. Ft.
I-5	18" x 12" V's (V.S.P.)	2	Units
I-6	12" Pipe removed & stored	190	Lin. Ft.
I-6	18" Pipe removed & stored	60	Lin. Ft.
I-6	24" Pipe removed & stored	100	Lin. Ft.
I-8	Manholes (I-8-M.H.#1)	4	Units
I-8	Manhole (I-8-M.H.#1) placed on existing masonry	1	Unit
I-8	Inlets using existing castings (I-8-C.B.#1-2)	12	Units
I-8	Catch Basins (I-8-C.B.#1-2)	4	Units
I-8	Inlets (I-8-I#5)	8	Units

20

30

