

GENERAL SUMMARY

FED. RD. DIVISION	STATE	PROJECT	8
2	OHIO		48

LAKE COUNTY
LAK.-306-5.56

ITEM	SHEET NUMBER																	ITEM	GRAND TOTAL	UNIT	DESCRIPTION	
	4	5	6	10	11	12	13	14	15	17	18	19	20	21	22							
																					DRAINAGE	
I-1							1694	2,381	2,132									I-1	6207	LIN.FT.	6" PIPE, CLASS I-3	
I-1							216	34										I-1	250	LIN.FT.	12" PIPE, CLASS B-1	
I-1																		I-1	242	LIN.FT.	12" PIPE, CLASS F-4	
I-1							124	224	250								242	I-1	598	LIN.FT.	12" PIPE, CLASS J-1	
I-1							210		145									I-1	355	LIN.FT.	15" PIPE, CLASS B-1	
I-1											164						340	I-1	504	LIN.FT.	15" PIPE, CLASS F-4	
I-1											100							I-1	100	LIN.FT.	18" PIPE, CLASS A-1, SEC. M-6.6(d). UNDER RAILROAD	
I-1							200	410				68						I-1	68	LIN.FT.	18" PIPE, CLASS A-1, SEC. M-6.6(b) OR SEC. M-6.8(b) OR SEC. M-6.4(d)	
I-1																		I-1	610	LIN.FT.	18" PIPE, CLASS B-1	
I-1																		I-1	143	LIN.FT.	18" PIPE, CLASS E-1	
I-1																		I-1	268	LIN.FT.	18" PIPE, CLASS J-1	
I-1																		I-1	370	LIN.FT.	21" PIPE, CLASS B-1	
I-1																		I-1	190	LIN.FT.	24" PIPE, CLASS B-1	
I-1																		I-1	174	LIN.FT.	27" PIPE, CLASS B-1	
I-1																		I-1	393	LIN.FT.	30" PIPE, CLASS B-1	
I-1																		I-1	325	LIN.FT.	30" PIPE, CLASS E-1	
I-1																		I-1	180	LIN.FT.	30" PIPE, CLASS J-1	
I-1																		I-1	40	LIN.FT.	36" PIPE, CLASS B-1	
I-2																		I-2	2.9	CUYD.	MASONRY	
I-5																		I-5	34	EACH	6" PIPE SPECIALS, CLASS I-3	
I-5							8	13	13									I-5	1	EACH	18" PIPE SPECIALS, CLASS B-1	
I-5																		I-5	1	EACH	15" PIPE SPECIALS, CLASS F-4	
I-8																		I-8	2	EACH	STANDARD NO. 2-2B CATCH BASINS	
I-8																		I-8	5	EACH	STANDARD NO. 3 CATCH BASINS	
I-8																		I-8	27	EACH	STANDARD NO. 3-A CATCH BASINS	
I-8																		I-8	19	EACH	STANDARD NO. 1 MANHOLES	
I-8																		I-8	3	EACH	MANHOLES ADJUSTED TO GRADE	
I-9																		I-9	670	LIN.FT.	STONE UNDERDRAINS, NO. 2	
I-10																		I-10	57	CUYD.	DUMPED ROCK CHANNEL PROTECTION	
I-16																		I-16	7	EACH	INLETS ABANDONED	
L-10																		L-10	500	SQ.YD.	SODDING	
																			LUMP	LUMP	CONSTRUCTION LAYOUT STAKES	
																			I-3	LUMP	LUMP	MAINTAINING TRAFFIC