

SIGNING SUB SUMMARY

SHEET No.	STATION	LOCATION	OFFSET	RIGHT	LEFT	ITEM 630 SIGNS															ITEM 630 GROUND MOUNTED SUPPORTS			ITEM 630																													
						SIGN INSTALLATION REQUIRED															No. OF POST REQ'D	No. 4 POST, ONE WAY	No. 3 POST	No. 4 POST	SIGNS, FLAT SHEET	SIGNS, FLAT SHEET TYPE G	SIGN, EXTRUSHEET TYPE G	REMOVAL OF GROUND MOUNTED SIGN AND RE-ERECTION																									
						R-31FF-48	R-38R-24	M-45--42				M-37-24	R-31K-36	R-121-24					M-2-24-3	R-31G-36													R-41A-36																				
						EACH															EACH	LINEAR FEET	SQ.F.T.	SQ.F.T.		SQ.F.T.	EACH																										
	22+10	RT306	55	✓																		2	13/13	7.5																													
	23+62	RT306	46	✓																		2	13/13	7.5																													
	0+64	RAMP F-4	10	✓		1																1	13		9																												
	25+55	RT306	36	✓	1																	2	13/13	10																													
	26+31	RT306	46	✓																		2		15/15				17.5																									
	27+30	RT306	34	✓	1																	2	13/13	10																													
	27+82	RT306	46	✓	1																	2	13/13	10																													
	32+45	RT306	46	✓	1																	2	13/13	10																													
	32+75	RT306	34	✓																		2		15/15				17.5																									
	34+48	RT306	46	✓	1																	2	13/13	10																													
	14+78	RAMP F-1	14	✓		1																1	13		9																												
	35+50	RT306	34	✓																		2	13/13	7.5																													
	37+00	RT306	46	✓																		1	13	7																													
	1+05	RAMP F-5	50	✓																		2	14	13	7.5				2																								
	3+70	RAMP F-5	18	✓																		2		13/13	13.5																												
	TOTALS																					26	*14	*247	*99	*80	*39		*35																								

SIGN LOCATION					ITEM 630											EXISTING SIGNS REQUIRING WORK										
SHEET No.	STATION	LOCATION	OFFSET	RT. OR LT.	R-31E	R-150	R-121	M-21	M-40	M-2	R-38R-24	R-121-24	R-31K-36	R-31Q	M-37	GH-1	ITEM 630 REMOVAL OF GROUND MOUNTED POST SUPPORT & STORAGE	ITEM 630 REMOVAL OF GROUND MOUNTED SIGN & STORAGE	ITEM 630 REMOVAL OF OVERHEAD MOUNTED SIGN & REERECTION	ITEM 630 REMOVAL OF OVERHEAD SIGN SUPPORT & STORAGE TYPE TC-12.30	ITEM 631 REMOVAL OF LUMINAIRE, AND REERECTION	ITEM 631 SIGN WIRED	ITEM 631 PHOTOELECTRIC CONTROL	ITEM 631 REMOVAL OF DISCONNECT SWT. AND REERECTION	ITEM 630 SIGN ATTACHMENT ASSEMBLY	
					EACH											EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH		
-	23+20	RT.306	43	RT.	1												2	1								
-	23+80	RT.306	43	RT.	1												2	1								
-	24+11	RT.306	46	RT.											1				2	1	2	2	1		4	
-	0+85	RAMP N	66	RT.		1	1										1	2								
-	26+31	RT.306	36	LT.				1	1	1							2	3								
-	27+20	RT.306	37	LT.										1			1	1								
-	32+75	RT.306	35	LT.				1	1	1							2	3								
-	14+40	RAMP J	45	LT.							1	1					1	2								
-	33+00	RT.306	34	LT.									1				2	1								
-	34+92.5	RT.306	39	LT.											1				2	1	2	2	1		4	
-	35+50	RT.306	38	RT.										1			1	1								
-	36+40	RT.306	37	RT.						1					1		2	2								
	TOTALS					2	1	1	2	2	3	1	1	1	2	1	2	*16	*17	*4	*2	*4	*4	*2	*2	*8

* THESE QUANTITIES HAVE BEEN CARRIED TO THE TRAFFIC CONTROL GENERAL SUMMARY SHEET No. 48 .

NOTE: INTEGRAL BALLASTS ARE TO BE INCLUDED IN PAY ITEM 631 REMOVAL OF LUMINAIRE, DISCONNECT SWITCH AND REERECTION.