

GENERAL SUMMARY

ITEM	SHEET NUMBER																				ITEM	ITEM EXT.	QUANT.	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION	
	14	15	45	46	47	50	56	66	67	74	75	76	77	78	79	80	81										
201	LUMP																					201	11000	LUMP		CLEARING & GRUBBING	
202								LUMP														202	11000	LUMP		STRUCTURES REMOVED	
202			758	3876						110	171	512	1171	794	253							202	23000	7645	SQ. YD.	PAVEMENT REMOVED	
202								11356	13444													202	30000	24800	SQ. FT.	WALK REMOVED	
202									25													202	32000	25	LIN. FT.	CURB REMOVED	
202			70	98																		202	32500	168	LIN. FT.	CURB AND GUTTER REMOVED	
202								7308	1043													202	35100	8351	LIN. FT.	PIPE REMOVED, 24" & UNDER	
202								226														202	35200	226	LIN. FT.	PIPE REMOVED, OVER 24"	
202								82														202	35401	82	LIN. FT.	PIPE REMOVED FOR STORAGE, OVER 24" AS PER PLAN	16
202								473														202	38000	473	LIN. FT.	GUARDRAIL REMOVED	
202								4	4													202	58000	8	EACH	MANHOLE REMOVED	
202									7	13												202	58100	20	EACH	CATCH BASIN REMOVED	
203		2500								294	244	292	415	228	239	83206						203	12000	87418	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
203		2500														4947						203	20000	7447	CU. YD.	EMBANKMENT	
203			79465	5225	3642																	203	50000	88332	SQ. YD.	SUBGRADE COMPACTION	
604																						604	38500	25	EACH	MONUMENT ASSEMBLY	
608										119,104												608	10000	119,104	SQ. FT.	4" CONCRETE WALK	
608										22												608	50000	22	EACH	CURB RAMP TYPE 1	
608										34												608	51000	34	EACH	CURB RAMP TYPE 2	
EROSION CONTROL																											
207	7500																					207	10000	7500	SQ. YD.	TEMPORARY SEEDING & MULCHING	
207	1000																					207	30000	1000	LIN. FT.	FILTER FABRIC FENCE	
207	100																					207	50000	100	CU. YD.	TEMPORARY BENCHES, DIKES, DAMS AND SEDIMENT BASINS	
207	1050																					207	70000	1050	EACH	STRAW OR HAY BALES	
601	10																					601	34200	10	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITHOUT FILTER	
601										8												601	11000	8	SQ. YD.	RIPRAP USING 6" REINFORCED CONCRETE SLAB	
601										7												601	32100	7	CU. YD.	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
601		10																				601	32300	10	CU. YD.	ROCK CHANNEL PROTECTION, TYPE D WITH FILTER	
653																2081						653	10000	2081	CU. YD.	TOPSOIL FURNISHED AND PLACED	
659	2000																					659	14000	2000	SQ. YD.	REPAIR SEEDING AND MULCHING	
659	1.3															3.4						659	20000	4.7	TON	COMMERCIAL FERTILIZER	
659																16.9						659	30000	16.9	TON	AGRICULTURAL LIMING	
659																31,458						660	30000	37458	SQ. YD.	SODDING	
659	70																					659	35000	70	M GAL	WATER	
660	20																					659	40000	20	M SQ. FT.	MOWING	