

# GENERAL

## PROJECT DESCRIPTION

THIS PROJECT INVOLVES THE RESURFACING OF SR 2 AND SR 44 AT THE LOCATIONS DETAILED IN THE PLANS. PARTIAL AND FULL DEPTH PAVEMENT REPAIRS, PAVEMENT MARKINGS, GUARDRAIL REPLACEMENT, MINOR BRIDGE WORK AND RAISED PAVEMENT MARKERS ARE ALSO INCLUDED.

## RIGHT OF WAY

ALL WORK SHALL BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY OR EASEMENTS.

## EXISTING TYPICAL SECTIONS

EXISTING TYPICAL SECTIONS HAVE BEEN TAKEN FROM THE RECORDS AND ARE BELIEVED TO REPRESENT THE EXISTING PAVEMENT, BUT THE STATE OF OHIO DOES NOT GUARANTEE THE ACCURACY OF THE SAME.

FOR FURTHER INFORMATION IN REGARD TO THE EXISTING TYPICAL SECTIONS, THE CONTRACTOR SHALL REFER TO THE PREVIOUS CONSTRUCTION PLANS.

THESE PLANS MAY BE REVIEWED AT THE

OHIO DEPARTMENT TRANSPORTATION  
DISTRICT 12 OFFICE  
5500 TRANSPORTATION BOULEVARD  
GARFIELD HEIGHTS, OHIO 44125

## CONVERSION OF METRIC STANDARD DRAWINGS

THE METRIC STANDARD DRAWINGS REFERENCED IN THIS PLAN SHALL BE CONVERTED TO ENGLISH UNITS USING THE SI (METRIC) TO ENGLISH CONVERSION FACTORS PROVIDED IN SECTION 109.011 OF THE 1997 CONSTRUCTION AND MATERIALS SPECIFICATIONS. THE APPENDIX OF ASTM E 380 SHALL BE UTILIZED FOR ANY ADDITIONAL CONVERSION FACTORS REQUIRED. CONVERSIONS SHALL BE APPROPRIATELY PRECISE AND SHALL REFLECT STANDARD INDUSTRY ENGLISH VALUES WHERE SUITABLE.

## CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK FOR ITEMS DESIGNATED BY PLAN NOTE TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER. THE ACTUAL WORK LOCATIONS AND QUANTITIES USED FOR SUCH ITEMS SHALL BE INCORPORATED INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

## WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

## EQUIPMENT AND MATERIAL STORAGE

IN ORDER TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC THE CONTRACTOR'S ATTENTION IS DIRECTED TO 614.03. IN ADDITION THE FOLLOWING PROVISIONS SHALL APPLY:

- 1) ANY REMOVED ITEMS SHALL NOT BE STORED ON THE RIGHT OF WAY FOR MORE THAN THIRTY DAYS.
- 2) THE STORAGE OF EQUIPMENT, MATERIALS, AND VEHICLES WITHIN THE HIGHWAY RIGHT OF WAY WILL BE PERMITTED. THE NUMBER OF AREAS AND EXACT LOCATIONS SHALL BE APPROVED BY THE ENGINEER.
- 3) ALL DISTURBED AREAS SHALL BE RETURNED TO THEIR ORIGINAL CONDITION AT NO EXPENSE TO THE STATE.

## WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

## ITEM 806 - FIELD OFFICE, TYPE C

A TYPE C FIELD OFFICE IS REQUIRED FOR THIS PROJECT.

## ELEVATION DATUM

ALL ELEVATIONS ARE BASED ON U. S. G. S. DATUM.

## ALTERNATE METHODS

IF THE CONTRACTOR SO ELECTS, HE MAY SUBMIT ALTERNATE METHODS FOR THE MAINTENANCE OF TRAFFIC, PROVIDED THE INTENT OF THE PROVISIONS IS FOLLOWED AND NO ADDITIONAL INCONVENIENCE TO THE TRAVELING PUBLIC RESULTS THERE FROM. NO ALTERNATE PLAN SHALL BE PLACED INTO EFFECT UNTIL APPROVAL HAS BEEN GRANTED IN WRITING, BY THE DIRECTOR.

## COOPERATION BETWEEN CONTRACTORS

THE CONTRACTOR SHALL COOPERATE AND COORDINATE HIS/HER OPERATIONS WITH THE CONTRACTORS ON OTHER PROJECTS THAT MAY BE IN FORCE DURING THE LIFE OF THE CONTRACT. NO WAIVER OF ANY PROVISIONS OF 105.07 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS IS INTENDED.

THE CONTRACTOR IS INFORMED THAT A CONSTRUCTION PROJECT ON SR - 2 IN THE CITY OF MENTOR (LAK-2-6.12, PID 19530) ADJACENT TO THE SUBJECT PROJECT MY BE UNDER CONSTRUCTION AT THE SAME TIME. ALL MOT PROVISIONS SHALL BE COORDINATED WITH THIS PROJECT.

## UTILITY OWNERSHIP

THE FOLLOWING UTILITIES AND OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT. THE OHIO DEPARTMENT OF TRANSPORTATION HAS USED THE BEST AVAILABLE INFORMATION TO DETERMINE THE UTILITY COMPANIES SERVING THIS AREA, BUT CANNOT GUARANTEE THE UTILITY COMPANY LIST IS COMPLETE.

OHIO DEPARTMENT OF  
TRANSPORTATION  
5500 TRANSPORTATION BLVD.  
GARFIELD HEIGHTS, OHIO 44125  
(216) 581-2100

AMERITECH  
13630 LORAIN AVE. 4TH FLOOR  
CLEVELAND, OH 44111  
(216) 476-6142

CITY OF PAINESVILLE  
SANITARY SEWERS  
7 RICHMOND STREET  
PAINESVILLE, OH 44077  
(216) 352-9301

CITY OF PAINESVILLE  
WATER  
7 RICHMOND STREET  
PAINESVILLE, OH 44077  
(216) 352-9301

THE ILLUMINATING CO.  
6896 MILLER RD  
BRECKSVILLE, OH 44141  
(440) 546-8748

CITY OF PAINESVILLE  
ELECTRIC  
7 RICHMOND STREET  
PAINESVILLE, OH 44077  
(216) 352-9301

EAST OHIO GAS CO.  
1201 E. 55TH ST  
CLEVELAND, OH 44103  
(216) 736-6755

LAKE COUNTY DEPARTMENT  
OF UTILITIES - SANITARY  
ADMINISTRATION BUILDING  
105 MAIN ST  
PAINESVILLE, OH 44060  
(216) 350-2649

LAKETRAN  
555 LAKESHORE BLVD  
PAINESVILLE, OH 44077  
(440) 350-1000

## ITEM 623 - CONSTRUCTION LAYOUT STAKES, AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF 623, THIS ITEM SHALL BE USED TO PROVIDE THE SURVEY OF THE ASPHALT BRIDGE TRANSITIONS AS REQUIRED BY THE NOTES ON SHEET 52.

PRIOR TO THE PLANING OF PAVEMENT BENEATH ALL OVERHEAD STRUCTURES, A LICENSED SURVEYOR SHALL MEASURE THE VERTICAL CLEARANCES AND DOCUMENT THE MEASUREMENTS ON AN APPROVED OHIO DEPARTMENT OF TRANSPORTATION FORM AVAILABLE FROM THE DISTRICT BRIDGE OFFICE. THE MEASUREMENTS SHALL BE TAKEN AT THE LOCATIONS INDICATED ON THE APPROVED ODOT FORM AND SUBMITTED TO THE PROJECT ENGINEER. AFTER THE NEW PAVING HAS BEEN COMPLETED, A REGISTERED SURVEYOR AGAIN SHALL TAKE VERTICAL CLEARANCE MEASUREMENTS AT LOCATIONS INDICATED ON THE APPROVED ODOT FORM. THESE FINAL MEASUREMENTS SHALL BE RECORDED ON THE FORM AND SUBMITTED TO THE PROJECT ENGINEER AND THE DISTRICT BRIDGE ENGINEER. THE RECORD SHALL BEAR THE STAMP OR SEAL OF THE LICENSED SURVEYOR WHO HAS TAKEN THE MEASUREMENTS AND WILL VERIFY THAT VERTICAL CLEARANCES HAVE BEEN PRESERVED.

CALCULATED  
EMK  
CHECKED  
LDH

GENERAL NOTES

LAKE COUNTY  
LAK-2/ 44-13.05/ 4.14

9  
93

PLOTTED FROM: I:\PROJECTS\18391\dgn\18391.dgn