

I:\PROJECTS\141839\B&N\PLANS\21365\GO.DGN 14-AUG-2001 12:55PM fkonopka

REF NO.	SHEET NO.	STATION		SIDE	202					203			254	202	301	304	305	407		CALCULATED	CHECKED	
					PAVEMENT REMOVED	CATCH BASIN REMOVED	CATCH BASIN ABANDONED	GUARDRAIL REMOVED	CURB REMOVED	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT	SUBGRADE COMPACTION	LINEAR GRADING	PAVEMENT PLANING, BITUMINOUS, 1.25"	WEARING COURSE REMOVED, AS PER PLAN	7" BITUMINOUS AGGREGATE BASE, PG64-22	6" AGGREGATE BASE, AS PER PLAN	9" CONCRETE BASE, AS PER PLAN	TACK COAT @ 0.1 GAL/SQ.YD.			TACK COAT FOR INTERMEDIATE COURSE @ 0.05 GAL/SQ.YD.
		FROM	TO			SQ. YD.	EACH	EACH	LIN. FT.	LIN. FT.	CU. YD.	CU. YD.	SQ. YD.	STA.	SQ. YD.	SQ. YD.	CU. YD.	CU. YD.	SQ. YD.	GAL.	GAL.	
		JACKSON STREET																				
		6+40.00	7+62.00							123	21			2		7		6	32	3	2	
		8+57.00±	8+73.00±							15	5			1				2	7	1	1	
		11+12.00±	11+20.00±							12	3			1				1	5	1	1	
		12+11.93	13+50.00			23				139	21			2				6	32	3	2	
		8+73.00	8+86.00±												1							
		10+99.00	11+12.00±												1							
		FERN DRIVE																				
		6+50.00	7+75.00			23				126	55		94	2	334		5	15		42	5	
		7+75.00	8+64.00±			38	3			114	48		77	2			12	12	71	24	12	
		8+17.00	8+64.00±												44							
		RAMP 1																				
		7+05.00	7+50.00										41			95		6	33	13	7	
		7+50.00	12+25.00										753			1002		117	674	168	84	
		12+25.00	14+05.00				1	1		1			545			381		88	514	90	45	
		14+05.00	14+68.00							63			144			155		25	144	31	16	
		14+68.00	15+25.00±						37.50	88			57			263		14	72	34	17	
		7+05.00	15+25.00±								432	1479										
TOTALS CARRIED TO GENERAL SUMMARY						84	4	1	37.50	681	585	1479	1711	10	380	1903	17	292	1584	410	192	

ESTIMATED QUANTITIES

LAKE COUNTY
LAK-2 / 44-13.05 / 4.14