

* - IN PLACE OF LANE LINE

CALCULATED
EMK
CHECKED
LDH

LOCATION AND STATION		828										621					
		EDGE LINES		LANE LINES	CHANNELIZING LINES		STOP LINES	CROSSWALK LINES	TRANSVERSE LINES (WHITE)	LANE ARROWS	WORD ON PAVEMENT 96"	RAISED PAVEMENT MARKER, INSTALLATION ONLY					
		WHITE LIN. FT.	YELLOW LIN. FT.	LANE LINES LIN. FT.	GORE LIN. FT.	* LIN. FT.	STOP LINES LIN. FT.	CROSSWALK LINES LIN. FT.	TRANSVERSE LINES (WHITE) LIN. FT.	LANE ARROWS EACH	WORD ON PAVEMENT 96" EACH	W EACH	W/R EACH	Y/R EACH			
SR-2 WESTBOUND																	
625+55.00	627+15.00	160	160	160	320			185				1	8				
627+15.00	629+95.00	280	280	560								6					
629+95.00	657+75.00	2780	2780	2780								23					
SR-44 NORTHBOUND																	
31+66.00	67+00.00	3534	3534	3534								30					
67+00.00	68+82.00	182	182	364								4					
68+82.00	70+08.00	126	126	126	252			93				1	7				
70+08.00	83+73.00	1365	1365	1365								12					
83+73.00	85+93.00	440	220	220	220							1	3				
85+93.00	87+94.00	201	201	402								4					
87+94.00	121+52.46 BK	3358	3358	3358								28					
121+67.42 AH	164+22.00	4255	4255	4255			40					36					
34+40.00	35+45.00					105	35			2	1						
54+81.00	56+11.00					130	35			2	1						
163+85.00							25										
SR-44 SOUTHBOUND																	
31+66.00	63+43.00	3177	3177	3177								27					
63+43.00	65+57.00	214	214	428								4					
65+57.00	67+84.00	454	227	227	227							2	6				
67+84.00	81+68.00	1384	1384	1384								12					
81+68.00	83+17.00	149	149	149	298			98				1	8				
83+17.00	84+74.00	157	157	314								4					
84+74.00	121+52.46 BK	3678	3678	3678								31					
121+67.42 AH	164+22.00	4255	4255	4255								36					
36+40.00							25										
57+06.00	58+36.00					105	35			2	1						
99+88.00	101+18.00					130	11			2	1						
120+73.00	121+52.46 BK					130	11			2	1						
121+67.42 AH	122+17.96																
RAMP A, SR-2		23	23														
RAMP D, SR-2		29	29			29	25										
BLACKBROOK RD.		50					28										
RAMP A, SR-44																	
7+85.00	13+70.00	870	800														10
RAMP B, SR-44																	
4+40.00	11+70.00	730	730				35										10
RAMP C, SR-44																	
10+10.00	17+80.00	770	770				35										9
RAMP D, SR-44																	
7+55.00	14+75.00	850	780					100									9
SHEET TOTAL		33471	32834	30736	1317	629	340	100	376	10	5	263	32	38			
		= 12.56 MILE		= 5.82 MILE		1946						**		333			

** QUANTITY CARRIED TO SHEET 66

PLOTTED FROM: I:\PROJECTS\Pid18391\dgn\18391tsa.dgn

PAVEMENT MARKING / RAISED PAVEMENT MARKER SUB-SUMMARY

LAKE COUNTY LAK-2 / 44-13.05 / 4.14