

SHEET NUMBER

NHS = SR-2, STA 586+22.12 TO STA 612+09.32
 NHS = SR-44, STA 233+00.00 TO STA 343+55.33
 STP = SR-2, STA 612+09.32 TO STA 657+25.10
 NHS = SR-44, STA 31+66.10 TO STA 164+34.08

SHEET NUMBER										ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
29	30	50P	63	64	65	82	NHS	STP							
			218				196	22	620	10300	218	EACH	DELINEATOR, TYPE C, POST MOUNTED		
			150				128	22	620	15300	150	EACH	DELINEATOR, TYPE D, POST MOUNTED		
			683				592	91	621	00200	683	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY	63	
			12				12		621	00301	12	EACH	PRISMATIC RETROREFLECTOR, AS PER PLAN	63	
							1		625	00500	1	EACH	CONNECTOR KIT, TYPE II		
							1		625	00600	1	EACH	CONNECTOR KIT, TYPE III		
							1		625	18200	1	EACH	BRACKET ARM, 15'		
						100	100		625	23400	100	LIN.FT.	NO. 10 AWG POLE AND BRACKET CABLE		
							1		625	26250	1	EACH	LUMINAIRE, CONVENTIONAL, 200 W, HPS, TYPE II, 480 V		
							1		625	32000	1	EACH	GROUND ROD		
286	102						370	18	626	00100	388	EACH	BARRIER REFLECTOR, TYPE A		
4	7						9	2	626	00200	11	EACH	BARRIER REFLECTOR, TYPE B		
						611	520	91	630	03100	611	LIN.FT.	GROUND MOUNTED SUPPORT, NO. 3 POST		
						131	131		630	06400	131	LIN.FT.	GROUND MOUNTED SUPPORT, S4X7.7 BEAM		
						183	144.5	38.5	630	06500	183	LIN.FT.	GROUND MOUNTED SUPPORT, W6X9 BEAM		
						60.5	60.5		630	08000	60.5	LIN.FT.	GROUND MOUNTED SUPPORT, W12X30 BEAM		
						15	15		630	08004	15	LIN.FT.	ONE WAY SUPPORT, NO. 3 POST		
						18	16	2	630	09000	18	EACH	BREAKAWAY BEAM CONNECTION		
						1	1		630	25500	1	EACH	COMBINATION OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 5, 20' ARMS		
						83.5	65.5	18	630	80102	83.5	SQ. FT.	SIGN, FLAT SHEET, TYPE G		
						498	498		630	80204	498	SQ. FT.	SIGN EXTRUSHEET, TYPE G		
						20	18	2	630	84500	20	EACH	GROUND MOUNTED BEAM SUPPORT FOUNDATION		
						1	1		630	84510	1	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION		
						12	10	2	630	84900	12	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL		
						51	45	6	630	85100	51	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION		
						67	56	11	630	86002	67	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL		
						2	2		630	86102	2	EACH	REMOVAL OF GROUND MOUNTED BEAM SUPPORT AND DISPOSAL		
						1	1		630	89702	1	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL		
						1	1		631	84000	1	EACH	SIGN SERVICE		
						1	1		631	84300	1	EACH	SIGN WIRED		
						1	1		631	85100	1	EACH	DISCONNECT SWITCH WITH ENCLOSURE, TYPE X		
						2	2		631	87154	2	EACH	BALLAST TYPE CMRI-175-120, INTEGRAL		
						2	2		631	89200	2	EACH	MERCURY VAPOR LUMINAIRE, TYPE TC-31.21 WITH 175 WATT LAMP		
					5		5		632	26501	5	EACH	DETECTOR LOOP, AS PER PLAN	63	
			710				710		642	30000	710	LIN.FT.	REMOVAL OF PAVEMENT MARKING		
			0.22		15.34	12.56	24.64	3.48	828	10000	28.12	MILE	EDGE LINE		
			0.08		6.06	5.82	10.14	1.82	828	10100	11.96	MILE	LANE LINE		
			0.09				0.09		828	10200	0.09	MILE	CENTER LINE		
			609		2211	1946	4446	320	828	10300	4766	LIN.FT.	CHANNELIZING LINE		
			114			340	454		828	10400	454	LIN.FT.	STOP LINE		
						100	100		828	10500	100	LIN.FT.	CROSSWALK LINE		
			85		635	376	911	185	828	10600	1096	LIN.FT.	TRANSVERSE LINE		
			837				837		828	10800	837	SQ.FT.	ISLAND MARKING		
			15			10	25		828	20300	25	EACH	LANE ARROW		
			8			5	13		828	20400	13	EACH	WORD "ONLY" ON PAVEMENT, 72"		

TRAFFIC CONTROL GENERAL SUMMARY

**LAKE COUNTY
LAK-2/44-13.05/4.14**

PLOTTED FROM: I:\PROJECTS\18391\18391.dgn