

GENERAL SUMMARY

COMPUTED BY: DGM
CHECKED BY: JAM

FHWA REGION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY
LAK-44-4.14

ITEM	SHEET NUMBER										TOTAL QUANT.		ITEM QUANT.	UNIT	DESCRIPTION							
	4		5		10		11		18		20					31		32		TOTAL	TOTAL	
	I	II	I	II	I	II	I	II	I	II	I	II				I	II	I	II			
DRAINAGE																						
603					163	442											163	442	603	605	L.F.	6" CONDUIT, TYPE F
603																			604	1	EACH	CATCH BASIN COVER, STANDARD NO. 4
604																			605	7,260	L.F.	AGGREGATE DRAIN, AS PER PLAN, USING N ^o 8 AGGREGATE
605																			605	690	L.F.	AGGREGATE DRAINS
605																			605	550	L.F.	6" UNCLASSIFIED PIPE UNDERDRAINS
605					20	30													SPECIAL	159	M. GAL.	WATER
SPCL					148	402													SPECIAL	55	EACH	UNDERDRAIN OPENINGS
SPCL					15.8	43.2																
SPCL					15	40																
TRAFFIC CONTROL																						
614							0.23	0.63									0.23	0.63	614	0.86	MI.	TEMPORARY LANE LINE, CLASS I, TYPE R TAPE
614							0.42	1.12									0.42	1.12	614	1.54	MI.	TEMPORARY EDGE LINES, CLASS I, TYPE R TAPE
614							10.62	18.13									10.62	18.13	614	28.75	MI.	TEMPORARY EDGE LINES, CLASS I
614							600										600		614	600	L.F.	TEMPORARY GORE MARKINGS, CLASS II
614							4.17	7.11									4.17	7.11	614	11.28	MI.	TEMPORARY LANE LINES, CLASS II
614							150										150		614	150	L.F.	TEMPORARY STOP LINES, CLASS I
621																			621	9.70	MILES	EDGE LINES
621																			621	3.73	MILES	LANE LINES, 4"
847																			847	2,150	L.F.	CHANNELIZING LINES, 947.02
847																			847	50	L.F.	STOP LINES, 947.02
847																			847	1,083	L.F.	TRANSVERSE LINES, 947.02
SPCL							73	197									73	197	SPECIAL	270	EACH	REPLACEMENT DRUMS
SPCL							59	161									59	161	SPECIAL	220	S.F.	REPLACEMENT SIGNS
630																			630	2.46	C.Y.	CONCRETE FOR EMBEDDED FOUNDATION
630																			630	58	L.F.	GROUND MOUNTED SUPPORTS, W10x22 BEAM
630																			630	1	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND REERECTION
630																			630	2	EACH	REMOVAL OF GROUND MOUNTED BEAM SUPPORT
STRUCTURES																						
SPCL																				710	S.F.	PATCHING CONCRETE STRUCTURE WITH SUPERIOR BONDING MATERIALS
SPCL																				2,029	S.Y.	SEALING OF CONCRETE SURFACES (EPOXY)(SEE PROPOSAL NOTE)
SPCL																				14	HOURS	LAW ENFORCEMENT OFFICER WITH PATROL CAR
SPCL							14	36												50		
614																			614	LUMP		MAINTAINING TRAFFIC
619																			619	LUMP		FIELD OFFICE
623																			623	LUMP		CONSTRUCTION LAYOUT STAKES
624																			624	LUMP		MOBILIZATION