

GENERAL SUMMARY

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

18
35

LAKE COUNTY
LAK-44-7.11

ITEM	SHEET NUMBER																		SUB TOTAL			ITEM	QUANT.	UNIT	DESCRIPTION	
	11		9		14		15		16		22		24		27		100% State	PARTICIPATION I	PARTICIPATION III	PARTICIPATION II						
	I	II	I	II	I	II	I	II	I	II	I	II	I	II	I	II										
																								TRAFFIC CONTROL		
630																					630	40	S.F.	SIGNS, EXTRU SHEET		
630																					630	36	S.F.	SIGNS, FLAT SHEET		
630																					630	127	L.F.	GROUND MOUNTED SUPPORT, NO.4 POST		
630																					630	2	EACH	REMOVAL OF GROUND MOUNTED SIGNS		
847																					847	4.54	MILES	EDGE LINES, 947.02		
847																					847	1.92	MILES	LANE LINES, 4-INCH, 947.02		
847																					847	475	L.F.	CHANNELIZING LINES, 947.02		
847																					847	105	L.F.	STOP LINES, 947.02		
847																					847	124	L.F.	TRANSVERSE LINE 947.02		
847																					847	400	L.F.	DOTTED LINES, 4-INCH, 947.02		
630																					630	2	EACH	REMOVAL OF GROUND MOUNTED POST. CLEAN SUPPORTS		
																								DRAINAGE		
603																					603	88	L.F.	6" CONDUIT, TYPE F		
605																					605	608	L.F.	AGGREGATE DRAINS		
605																					605	138	L.F.	6" UNCLASSIFIED PIPE UNDERDRAINS		
605																					605	1,830	L.F.	AGGREGATE DRAIN, AS PER PLAN, USING NO.8 AGGREGATE		
SPEC.																					SPECIAL	23	EACH	UNDERDRAIN OPENINGS		
SPEC.																					SPECIAL	26	M. GAL.	WATER		
604																					604	1	EACH	CATCH BASIN ADJUSTED TO GRADE		
																								STRUCTURES		
516																					516	184	L.F.	VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINTS, AS PER PLAN		
845																					845	1,483	S.Y.	LATEX MODIFIED CONCRETE OVERLAY, 1 1/4" THICKNESS		
845																					845	111	C.Y.	LATEX MODIFIED CONCRETE OVERLAY, (VARIABLE THICKNESS)		
845																					845	2	C.Y.	FULL DEPTH REPAIR		
SPEC.																					SPECIAL	1,150	S.Y.	SEALING OF CONCRETE SURFACES		
SPEC.																					SPECIAL	60	S.F.	PATCHING CONCRETE STRUCTURES WITH MAGNESIUM PHOSPHATE CONCRETE		
																								GENERAL		
Spa.	40	10																			40	10	Special	50	Hours	Law Enforcement Officer With Patrol Car
619																					LUMP	LUMP	LUMP	619	LUMP	FIELD OFFICE
623																					LUMP	LUMP	LUMP	623	LUMP	CONSTRUCTION LAYOUT STAKES
624																					LUMP	LUMP	LUMP	624	LUMP	MOBILIZATION
614																					LUMP	LUMP	LUMP	614	LUMP	Maintaining Traffic