

STATE OF OHIO  
DEPARTMENT OF HIGHWAYS  
APPROXIMATE ESTIMATE

TYPE T-71 & Structure

LAKE COUNTY

UNIT PRICE CONTRACT

S. R. NO. 44

For improving Section LAK-44-7.22, State Route No. 44 in Village of Grand River, and Mentor and Painesville Townships, Lake County, Ohio, in accordance with plans and specifications by grading, draining and paving with reinforced Portland cement concrete and by constructing:

Bridge No. LAK-44-0795, a concrete deck on continuous steel beams with concrete substructure (spans 52'-65'-65'-52', roadway 59' with 2'3" safety curbs and including a 3' median), State Route 283 over S.R. 44.

Project length = 12,720.02 ft. or 2.409 miles

Work LENGTH = 17,371.02 FT. OR 3.289 MILES.

WIDTH: PAVEMENT 2 at 25

FT. ROADWAY

REF. NO.	ITEM NO.	APPROXIMATE QUANTITIES	ITEM	UNIT PRICE		TOTAL	
				DOLLARS	CENTS	DOLLARS	CENTS
<b>ROADWAY</b>							
1	E-1	285,602	cu. yds. roadway excavation, Method "B", as per plan				
2	E-1	135,656	sq. yds. compacted subgrade				
3	E-4	1,600	cu. yds. granular borrow				
4	E-4	6,466	cu. yds. borrow				
5	E-8	4,912	sq. yds. removal and disposal of existing pavement				
6	E-9	lump sum	removal of trees and stumps				
7	E-11	1,623	M. gals. water				
8	E-12	1,395	lin. ft. pipe removed, 15" and under, as per plan				
9	E-12	28	lin. ft. pipe removed, over 15", as per plan				
10	I-8	21	each centerline reference monuments, as per plan				
11	I-8	1	each standard monument assembly				
12	I-15	6,475	lin. ft. guard rail, steel beam standard type (deep)				
13	L-9	238,746	sq. yds. seeding and protecting, as per plan				
14	L-9	21.90	tons commercial fertilizer (12-12-12)				
15	L-10	4,310	sq. yds. sodding				
16	L-10	230	sq. yds. sodding for special berm and slope protection				
17	M-10	11.74	tons calcium chloride furnished and applied				
18	S-15	lump sum	temporary runaround road, using Class "B" pavement, as per plan				
19	SS-18	19,233	lin. ft. fence, Type "A"				
20	T-10	500	cu. yds. traffic compacted surface course for maintaining traffic				
21	Special	4	hrs. fill compaction, using heavy pneumatic-tired roller				
22	<b>TOTAL ROADWAY</b>						
<b>BUILDING REMOVAL</b>							
23	E-10	lump sum	removal of 1½ story frame dwelling, Parcel No. 1-LA				
24	E-10	lump sum	removal of 1 story frame dwelling, Parcel No. 1-LA				

E.L. 2-6-189