

Lake COUNTY, SECTION LAK-44-7.22

REF. NO.	ITEM NO.	APPROXIMATE QUANTITIES	ITEM	UNIT PRICE		TOTAL	
				DOLLARS	CENTS	DOLLARS	CENTS
25	E-10	lump sum	removal of 1 story frame dwelling, Parcel No. 5-LA				
26	E-10	lump sum	removal of 1 story frame dwelling, Parcel No. 13-LA				
27	E-10	lump sum	removal of metal Quonset Hut (concrete floor), Parcel No. 14				
28	E-10	lump sum	removal of shed, Parcel No. 14				
29	E-10	lump sum	removal of 1 story block dwelling with garage, Parcel No. 15-LA				
30	E-10	lump sum	removal of 1 story frame dwelling, Parcel No. 18-LA				
31	E-10	lump sum	removal of 1 frame shed, Parcel No. 19				
32	E-10	lump sum	removal of concrete block garage, Parcel No. 22				
33	E-10	lump sum	removal of 2 story frame dwelling, Parcel No. 29				
34	E-10	lump sum	removal of 2 frame sheds, Parcel No. 29				
35	E-10	lump sum	removal of 1½ story frame dwelling, Parcel No. 33-LA				
36	E-10	lump sum	removal of 1 story frame garage and greenhouse, Parcel No. 36				
37	E-10	lump sum	removal of 1½ story frame dwelling, Parcel No. 39-LA				
38	E-10	lump sum	removal of 2½ story brick dwelling, patio and garage, Parcel No. 44-B-LA				
39	E-10	lump sum	removal of cinder block garage, Parcel No. 44B-LA				
40	E-10	lump sum	removal of frame garage, Parcel No. 44-B-LA				
41	E-10	lump sum	removal of screened patio, Parcel No. 47-LA				
42	E-10	lump sum	removal of house trailer (office), Parcel No. 55-LA				
43			<b>TOTAL BUILDING REMOVAL</b>				
			<b>DRAINAGE</b>				
44	E-3	337 cu. yds.	channel excavation				
45	I-1	52 lin. ft.	15" paved bituminous coated corrugated metal pipe, Sec. M-6.4(d), Class A-1				
46	I-1	40 lin. ft.	24" paved bituminous coated corrugated metal pipe, Sec. M-6.4(d), 12 gage, under railroad, Class A-1, as per plan				
47	I-1	178 lin. ft.	30" reinforced concrete pipe, Sec. M-6.6(b), or extra-strength vitrified sewer pipe, Sec. M-6.8(b), Class A-1				
48	I-1	156 lin. ft.	36" reinforced concrete pipe, Sec. M-6.6(c), Class A-1				
49	I-1	142 lin. ft.	48" paved bituminous coated corrugated metal pipe, Sec. M-6.4(d), Class A-1				
50	I-1	126 lin. ft.	48" reinforced concrete pipe, Sec. M-6.6(b), Class A-1				
51	I-1	272 lin. ft.	84" reinforced concrete pipe, Sec. M-6.6(b), Class A-1				
52	I-1	286 lin. ft.	84" heavy duty reinforced concrete culvert pipe, Sec. M-106.6(d), Class A-1				