

(c) Testing. Testing shall be performed by subjecting all new joints to the working pressure of the main for a sufficient length of time to allow for a thorough examination of the joints and elimination of leakage.

(d) Backfilling. Backfilling shall be performed as required under Sec. I-124.03 New Water Main.

(e) Disinfection. Disinfection shall be performed as required under Sec. I-124.03 New Water Main.

I-124.10 Service Boxes Adjusted to Grade. This item shall consist of adjusting existing service boxes to the grade shown on the Plans.

(a) Excavation. The Contractor shall excavate around each existing service box and stop, using special care so as to avoid injuring the stop, box or pipe.

(b) Adjusting to Grade. The service box shall be adjusted to grade. If the necessary adjustment is outside the design limits of the existing box, an extension shall be added or a new service box installed, as the Engineer shall direct. The adjusted, extended or new service box, shall not transmit shock or stress to the stop and shall be centered and plumb over the wrench nut of the stop.

(c) Backfilling. Backfilling shall be performed as required under Sec. I-124.03 New Water Main.

I-124.11 Water Meters and Boxes Removed and Reset. This item shall consist of removing and resetting existing water meters and boxes as shown on the Plans or as directed by the Engineer.

(a) Excavation. Excavation shall be performed as required under Sec. I-124.03 New Water Main.

(b) Removing and Resetting. The existing meter box shall be removed, the existing water meter disconnected and replaced with suitable connections, the line cut and water meter connected at the new location. The meter box shall be installed plumb and centered over the meter.

(c) Testing. Testing shall be performed by subjecting all new joints to the working pressure of the main for a sufficient length of time to allow for a thorough examination of the joints and elimination leakage.

(d) Backfilling. Backfilling shall be performed as required under Sec. I-124.03 New Water Main.

(e) Disinfection. Disinfection shall be performed as required under Sec. I-124.03 New Water Main.