metric units

GENERAL SUMMARY

SHEET NUMBER															ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET
6	16	18	20	21	22	23	24	25	26	27	28	29	31							
																			ROADWAY	
LUMP															201	11000	LUMP		CLEARING AND GRUBBING	
		21													202	35100	21	METER	PIPE REMOVED, 600 mm AND UNDER	
		113													202	38000	113	METER	GUARD RAIL REMOVED	
		1													202	58100	1	EACH	CATCH BASIN REMOVED	
					104	91	3	7	534	460	158	70			203	12000	1427	CU. METER	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
	381														203	50000	381	SQ. METER	SUBGRADE COMPACTION	
		58													606	13000	58	METER	GUARD RAIL, TYPE 5	
		1													606	25000	1	EACH	ANCHOR ASSEMBLY, TYPE A	
		1													606	26500	1	EACH	ANCHOR ASSEMBLY, TYPE T	
		2													606	35000	2	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 1	
												1			SPECIAL	690050100	1	EACH	MAILBOX SUPPORT SYSTEM, SINGLE	
																			EROSION CONTROL	
150															207	10000	150	SQ. METER	TEMPORARY SEEDING AND MULCHING	
90															207	30000	90	METER	FILTER FABRIC FENCE	
80															207	50000	80	CU. METER	TEMPORARY BENCHES, DAMS, AND SEDIMENT BASINS	
60															207	55500	60	SQ. METER	TEMPORARY DITCH PROTECTION	
50															207	70000	50	EACH	STRAW OR HAY BALES	
									446	201	83				601	32100	730	CU. METER	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
16															601	32200	16	CU. METER	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
7.5															659	20000	7.5	KILOGRAM	COMMERCIAL FERTILIZER	
2															659	35000	2	CU. METER	WATER	
185															659	40000	185	SQ. METER	MOWING	
			39	360	193	144	64	68	11						660	30000	879	SQ. METER	SODDING, UNSTAKED	
																			DRAINAGE	
5															603	01400	5	METER	150 mm CONDUIT, TYPE E, 707.33, 707.41 NON-PERFORATED, 707.42, 707.45	
5															603	01500	5	METER	150 mm CONDUIT, TYPE F, 707.33, 707.41 NON-PERFORATED, 707.42, 707.45	
													118		603	04400	118	METER	300 mm CONDUIT, TYPE B	
													3		604	04501	3	EACH	CATCH BASIN NO. 2-2B, AS PER PLAN	6
													1		604	34500	1	EACH	MANHOLE ADJUSTED GRADE	
																			PAVEMENT	
	38														301	46000	38	CU. METER	BITUMINOUS AGGREGATE BASE, PG 64-22	
	57											23			304	20000	80	CU. METER	AGGREGATE BASE	
	57											27			407	14000	84	LITER	TACK COAT FOR INTERMEDIATE COURSE	
	304											210			408	10000	514	LITER	BITUMINOUS PRIME COAT	
												38			411	10000	38	CU. METER	STABILIZED CRUSHED AGGREGATE	
	9											4			448	46020	13	CU. METER	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG 64-22	
	9											5			448	47020	14	CU. METER	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22	
	6														448	47081	6	SQ. METER	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, UNDER GUARDRAIL, PG 64-22, AS PER PLAN	6
	163														611	15001	163	SQ. METER	REINFORCED CONCRETE APPROACH SLAB, (T = 300 mm) AS PLAN	41

CALCULATED DEW
CHECKED JSK

GENERAL SUMMARY

LAK-528-11.024

14
49

FILE NAME: 12834GGA
DATE: 3-31-98 PS
PLOT: 1:1