



GENERAL SUMMARY

SHEET NUMBER				ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET
6	7	32						WATER WORK	
								TRAFFIC CONTROL	
		8		630	03100	8	METER	GROUND MOUNTED SUPPORT, NO. 3, 4.06 m LENGTH	
		1.35		630	80100	1.35	SQ. METER	SIGN, FLAT SHEET	
		5		630	84900	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
		3		630	86002	3	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
		0.64		642	00090	0.64	km	EDGE LINE	
		0.41		642	00290	0.41	km	CENTERLINE	
								TRAFFIC MAINTENENCE	
	10			614	13000	10	CU. METER	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
	50			614	13302	50	EACH	BARRIER REFLECTORS	
	50			614	13350	50	EACH	OBJECT MARKERS	
	0.56			614	21000	0.56	km	TEMPORARY CENTER LINE, CLASS I	
	1.10			614	22000	1.10	km	TEMPORARY EDGE LINE, CLASS I	
	LUMP			615	10000	LUMP		TEMPORARY ROAD	
	764			615	25001	764	SQ. METER	TEMPORARY PAVEMENT, CLASS B, AS PER PLAN A	7
	676			615	25001	676	SQ. METER	TEMPORARY PAVEMENT, CLASS B, AS PER PLAN B	7
	200			616	10000	200	CU. METER	WATER	
	2			616	20000	2	METRIC TON	CALCIUM CHLORIDE	
	302			622	40020	302	METER	PORTABLE CONCRETE BARRIER, 813 mm	
	19			622	40041	19	METER	PORTABLE CONCRETE BARRIER, 813 mm, BRIDGE MOUNTED, AS PER PLAN	37
				614	11000	LUMP		MAINTAINING TRAFFIC	
				623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
				624	100000	LUMP		MOBILIZATION	
				806	16000	12	MONTH	FIELD OFFICE, TYPE A	
				806	26000	12	MONTH	COMPUTER EQUIPMENT FOR FIELD OFFICE	