

FOR PLAN VIEWS SEE SHEETS 10 THRU 21
FOR TYPICAL SECTIONS SEE SHEET 3

PAVEMENT REPAIR SUB-SUMMARY

CALC. BY J.J.C.
DATE 1/93
CHKD. BY C.C.H.
DATE 1/93

LAK - 535 - 0.55

OHIO
FHWA REGION 5
76
90

PLAN NO. 271

PAVEMENT REPAIR					252	252	252
SHEET	REF.	LOCATION	LENGTH (FEET)	WIDTH (FEET)	FULL DEPTH RIGID PAV'T REMOVE & FLEX REPLACE TYPE I	FULL DEPTH RIGID PAV'T. REMOVE & FLEX REPLACE TYPE II	FULL DEPTH PAVEMENT SAWING
					SQ. YARDS	SQ. YARDS	L. F.
10	P-1	51+60, L AND R	7.3	27.0		21.9	54
10	P-2	53+65, L AND R	7.3	25.0		20.3	50
11	P-1	55+50, L AND R	7.3	27.0		21.9	54
11	P-2	56+50, L AND R	7.3	28.0		22.7	56
12	P-1	60+92 TO 61+65, R	73.0	10.2		82.7	146
12	P-2	61+85, L AND R	7.3	28.0		22.7	56
13	P-1	63+20, L AND R	7.3	28.0		22.7	56
13	P-2	66+00, L AND R	7.3	28.0		22.7	56
14	P-1	68+00, L AND R	7.3	28.0		22.7	56
14	P-2	70+00, L AND R	7.3	28.0		22.7	56
14	P-3	69+50 L AND R	7.3	28.0		22.7	56
15	P-1	72+00, L AND R	7.3	28.0		22.7	56
15	P-2	74+00, L AND R	7.3	28.0		22.7	56
16	P-1	78+50, L AND R	7.3	28.0		22.7	56
17	P-1	80+75, L AND R	7.3	28.0		22.7	56
17	P-2	83+00, L AND R	7.3	28.0		22.7	56
18	P-1	85+08, R TO 85+44, L	10.2	47.0		53.3	94
18	P-2	85+92 TO 86+31, L	10.2	39.0		44.2	78
18	P-3	86+56, L AND R	7.3	29.0	23.5		58
19	P-1	89+36 TO 89+76, L	40.0	10.2	45.3		80
19	P-2	89+ 42 TO 89+64, L	25.0	7.3	20.3		50
19	P-3	89+64, 41' L TO 21' L	11.0	7.3	8.9		22
20	P-1	92+00, L AND R	7.3	29.0	23.5		58
20	P-2	93+50, L AND R	7.3	29.0	23.5		58
21	P-1	95+30 TO 97+55, R	225.0	10.2	255.0		450
21	P-2	95+03, L AND R	7.3	29.0	23.5		58
21	P-3	95+49 TO 95+81, L	29.0	7.3	23.5		58
21	P-4	95+81, 32' L TO 10' L	10.0	7.3	8.1		20
21	P-5	95+85 5' L TO 20' R	25.0	7.3	20.3		
		PAVEMENT REPAIR SUB-SUMMARY					
		GRAND TOTAL			475.4	494.0	2110

CARRIED TO GENERAL SUMMARY

90483 MON 02/01/93 08:51:09 AM JACK FILES: PVREPSUM.PLT