

PLOTTED BY: ekallio
PLOTTED FROM: I:\PROJECTS\PID21525\DGN\21525gpa.dgn
21525GNA.DGN
31-AUG-2000 11:08

SCOPE OF PROJECT

PART 1

THE WORK PROPOSED FOR THIS PROJECT CONSISTS OF PLANING AND RESURFACING SR-608 IN CORCORD TOWNSHIP FROM SLM 0.38 TO SLM 0.99 AS DETAILED IN THE TYPICAL SECTIONS.

PART 2 & 3

THIS WORK SHALL INCLUDE REMOVING THE ASPHALT OVERLAY AT TWO CONDUITS UNDER IR-90 AND RESURFACING THE PAVEMENT TO ELIMINATE A "DIP" THAT HAS DEVELOPED.

UTILITIES OWNERSHIP

THE FOLLOWING UTILITIES AND OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THE PROJECT. THE OHIO DEPARTMENT OF TRANSPORTATION HAS USED THE BEST AVAILABLE INFORMATION TO DETERMINE THE UTILITY COMPANIES SERVING THIS AREA, BUT CANNOT GUARANTEE THE UTILITY COMPANY LIST IS COMPLETE.

THE ILLUMINATING CO.
4141 ROCKSIDE RD
SEVEN HILLS, OH 44131
ATTN: FRANK DIBBS
(216) 520-9579

THE OHIO DEPT. OF TRANSPORTATION
5500 TRANSPORTATION BLVD.
GARFIELD HTS., OH 44125
(216) 581-2333

THERE ARE NO UNDERGROUND UTILITIES SHOWN ON THIS PLAN. THE NATURE OF THE WORK REQUIRED BY THIS PROJECT WILL NOT AFFECT ANY KNOWN UNDERGROUND UTILITIES THAT EXIST UNDER OR ADJACENT TO THE WORK AREA.

EXISTING TYPICAL SECTIONS

EXISTING TYPICAL SECTIONS HAVE BEEN TAKEN FROM THE RECORDS AND ARE BELIEVED TO REPRESENT THE EXISTING PAVEMENT, BUT THE STATE OF OHIO DOES NOT GUARANTEE THE ACCURACY OF THE SAME.

FOR FURTHER INFORMATION IN REGARD TO THE EXISTING TYPICAL SECTIONS, THE CONTRACTOR SHALL REFER TO THE PREVIOUS CONSTRUCTION PLANS.

THESE PLANS MAY BE REVIEWED AT THE

OHIO DEPARTMENT TRANSPORTATION
DISTRICT 12 OFFICE
5500 TRANSPORTATION BOULEVARD
GARFIELD HEIGHTS, OHIO 44125

COOPERATION BETWEEN CONTRACTORS

THE CONTRACTOR SHALL COOPERATE AND COORDINATE HIS OPERATIONS WITH THE CONTRACTORS ON OTHER PROJECTS THAT MAY BE IN FORCE DURING THE LIFE OF THE CONTRACT. NO WAIVER OF ANY PROVISIONS OF 105.07 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS IS INTENDED.

RIGHT OF WAY

ALL WORK IS TO BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY.

FIELD OFFICE

THERE IS NO PAY QUANTITY PROVIDED FOR A FIELD OFFICE IN THESE PLANS.

CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIAL OR PERFORM WORK FOR THE PLAN ITEMS SET UP TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER.

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

CELLULAR PHONES

THE CONTRACTOR SHALL PROVIDE TWO (2) CELLULAR PHONES FOR USE BY ODOT ENGINEERS/SUPERVISORS/INSPECTORS.

PAYMENT FOR ALL MATERIAL, LABOR AND EQUIPMENT, INSTALLATION AND MAINTENANCE SHALL BE MADE AT THE CONTRACT BID PRICE FOR ITEM 690 - CELLULAR PHONE.

CALCULATED
ENK
CHECKED
LDH

GENERAL NOTES

LAKE COUNTY
LAK-608-0.38/VAR