

PLOTTED BY: fkonopka  
 PLOTTED FROM: J:\PROJECTS\PID21525\DGN\21525gga.dgn  
 PLOT SUBMITTED: 31-AUG-2000 10:39  
 21525GGA.DGN

SHEET NO.											
ITEM	4	5	7	7A	11	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN
202					3468	202	23500	3468	SQ. YD.	WEARING COURSE REMOVED	
202		77				202	54101	77	EACH	RAISED PAVEMENT MARKER REMOVED FOR STORAGE, AS PER PLAN	5
254					8376	254	01000	8376	SQ. YD.	PAVEMENT PLANING, BITUMINOUS	
254		800				254	01600	800	SQ. YD.	PATCHING PLANED SURFACE	
407					1186	407	10000	1186	GALLON	TACK COAT	
407					172	407	14000	172	GALLON	TACK COAT FOR INTERMEDIATE COURSE	
448					108	448	46010	108	CU. YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-28	
448					144	448	50001	144	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN	5
448					349	448	90000	349	CU. YD.	ASPHALT CONCRETE, MISC.: ASPHALT CONCRETE SURFACE COURSE, TYPE 1	5
604		2				604	39501	2	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	5
621				77		621	00200	77	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY	
642					1.48	642	00102	1.48	MILE	EDGE LINE, TYPE 2	
642					0.16	642	00202	0.16	MILE	LANE LINE, TYPE 2	
642					0.58	642	00302	0.58	MILE	CENTER LINE, TYPE 2	
614			30			614	13000	30	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
614					0.48	614	20100	0.48	MILE	TEMPORARY LANE LINE, CLASS I, 642 PAINT	
614					0.58	614	21100	0.58	MILE	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
614					0.58	614	21500	0.58	MILE	TEMPORARY CENTER LINE, CLASS II, 642 PAINT	
614					2.12	614	22100	2.12	MILE	TEMPORARY EDGE LINE, CLASS I, 642 PAINT	
614						614	11000	LUMP		MAINTAINING TRAFFIC	
623						623	10001	LUMP		CONSTRUCTION LAYOUT STAKES, AS PER PLAN	5
624						624	10000	LUMP		MOBILIZATION	
SPECIAL	2					SPECIAL	69086000	2	EACH	CELLULAR PHONE	4

CALCULATED  
 E.M.K.  
 CHECKED  
 LDH  
 GENERAL SUMMARY  
 LAKE COUNTY  
 LAK-608-0.38/VAR  
 12  
 12