

# MAINTENANCE OF TRAFFIC SUB-SUMMARY

WORK ZONE PAVEMENT MARKINGS SUB-SUMMARY			614	614	614
			TEMPORARY 4" DOUBLE YELLOW CENTER LINE CLASS I 740.05 TYPE C	TEMPORARY 4" EDGE LINE, WHITE, CLASS I 740.05 TYPE C	TEMPORARY STOP LINE, CLASS I, 740.05 TYPE C
PHASE	SIDE	STATION TO STATION	MILES	MILES	LIN. FT.
1 & 2	LT.	STA. 17+00 TO STA. 18+50	.03		
1 & 2	LT.	STA. 25+36 TO STA. 26+86	.03		
1	LT./RT.	STA. 19+00 TO STA. 20+00		.02	
1 & 2	LT./RT.	STA. 18+50			15
1 & 2	LT./RT.	STA. 25+36			12
2	LT./RT.	STA. 23+86 TO STA. 24+86		.02	
2	LT./RT.	STA. 19+19 TO STA. 19+67		.01	
1 & 2	LT./RT.	S.R. 608 STA. 19+00 (STA.10+25)			12
1 & 2	LT./RT.	S.R. 608 STA. 18+75 (STA. 0+25)			12
TOTAL			.06	.05	51

PORTABLE CONCRETE BARRIER			614	614	622	622
			OBJECT MARKER	BARRIER REFLECTOR, TYPE B2	PORTABLE CONCRETE BARRIER, 32"	PORTABLE CONCRETE BARRIER, 32", BRIDGE MOUNTED, UNANCHORED
PHASE	SIDE	STATION TO STATION	EACH	EACH	LIN. FT.	LIN. FT.
1	LT./RT.	STA. 19+00 TO STA. 21+43	22	11	240	
1	LT.	STA. 21+43 TO STA. 22+75	10	5		130
1	LT./RT.	STA. 22+75 TO STA. 24+73	16	8	200	
2	LT./RT.	STA. 19+20 TO STA. 21+37	20	10	220	
2	RT.	STA. 21+37 TO STA. 22+86	12	6		150
2	LT./RT.	STA. 22+86 TO STA. 24+83	16	8	200	
TOTALS			96	48	860	280

TEMPORARY PAVEMENT SUB-SUMMARY					615	615	
					TEMPORARY PAVEMENT, CLASS A	TEMPORARY ROADS	
PHASE	SIDE	STATION TO STATION	LENGTH	AVERAGE WIDTH	SQ. YD.	LUMP SUM	
1	RIGHT	S.R. 608 STA. 18+75 (STA. 0+00 TO 2+09.85)	209.85'	12.0'	271.0 *		
1	LEFT	STA. 22+61 TO STA. 23+88	127.0'	1.0'	127.0		
2	LEFT	S.R. 608 STA. 19+47 (STA. 10+00 TO 12+39.38)	239.38'	12.0'	275.3 *		
2	RIGHT	STA. 19+00 TO STA. 21+35.49	135.5'	4.0'	98.3 *		
2	RIGHT	STA. 22+85.35 TO STA. 24+55	169.65'	4.0'	67.3 *		
TOTALS					838.9		LUMP

\* AREA CALCULATED BY COMPUTER

THESE QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY.