SHEET NUMBER			PARTICIPATION					ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN
2	3	4				CITY	STATE						
												ROADWAY	
237.5						237.5		202	38000	237.5	LIN FT	GUARDRAIL REMOVED	
		97.2				28.5	68.7	203	60000	97.2	STATION	LINEAR GRADING	
250							250	SPECIAL	60450000	250	POUND	MISCELLANEOUS METAL	2
187.5						187.5		606	13000	187.5	LIN FT	GUARDRAIL, TYPE 5	
2						2		606	25000	2	EACH	ANCHOR ASSEMBLY, TYPE A	
												EROSION CONTROL	
50						15	35	670	40000	50	SQ YD	DITCH EROSION PROTECTION	
2							2	870	00100	2	EACH	SOIL ANALYSIS TEST	
20						6	14	870	00200	20	CU YD	PLACING TOPSOIL	
1500						450	1050	870	10000	1500	SQ YD	SEEDING AND MULCHING	
0.50						0.15	0.35	870	20000	0.50	TON	COMMERCIAL FERTILIZER	
0.50						0.15	0.35	870	30000	0.50	TON	AGRICULTURAL LIME	
2						0.60	1.40	870	35000	2	M GAL	WATER	
												PAVEMENT	
1000						300	700	251	01000	1000	SQ YD	PARTIAL DEPTH PAVEMENT REPAIR	
		120				20	100	254	01000	120	SQ YD	PAVEMENT PLANING, BITUMINOUS	
		1407.3				411.8	995.5	407	10000	1407.3	GALLON	TACK COAT	
		586.4				171.6	414.8	446	47011	586.4	CU YD	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-28, AS PER PLAN	2
		60				17.6	42.4	617	10100	60	CU YD	COMPACTED AGGREGATE, TYPE A	
		14073				4118	9955	822	10001	14073	SQ YD	HOT IN-PLACE RECYCLING, INTERMEDIATE COURSE, AS PER PLAN	2
												TRAFFIC CONTROL	
	1.84					0.54	1.30	828	10000	1.84	MILE	EDGE LINE	
	0.92						0.92	828	10200	0.92	MILE	CENTER LINE	
	25						25	828	10400	25	LIN FT	STOP LINE	
												MAINTENANCE OF TRAFFIC	
	10					3	7	410	10000	10	CU YD	TRAFFIC COMPACTED SURFACE, TYPE A	
	10					3	7	614	12460	10	EACH	WORK ZONE MARKING SIGN	
	10					3	7	614	13000	10	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
	1.84						1.84	614	21100	1.84	MILE	TEMPORARY CENTER LINE, CLASS 1, 642 PAINT	
	3.68					1.08	2.60	614	22100	3.68	MILE	TEMPORARY EDGE LINE, CLASS 1, 642 PAINT	
							LUMP	614	11000	LUMP		MAINTAINING TRAFFIC	
							LUMP	624	10000	LUMP		MOBILIZATION	

CALCULATED

CHECKED

GENERAL SUMMARY

LAK-615-0.22

I:\PROJECTS\Pid2514\DGN\2514GGA.dgn 01-NOV-2001 9:24AM jgrmoyse