SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
8		13	14	15	20	24		136								
															TRAFFIC CONTROL	
						8					626	00300	8	EACH	BARRIER REFLECTOR, TYPE A2	
								318.5			630	03100	318.5	LIN FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
								163.5			630	80102	163.5	SQ FT	SIGN, FLAT SHEET, TYPE G	
								25			630	84900	25	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
								15			630	85000	15	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
								19			630	86002	19	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
								11			630	86006	11	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE	
								1.18			828	10000	1.18	MILE	EDGE LINE	
								.82			828	10200	.82	MILE	CENTER LINE	
								100			828	10300	100	LIN FT	CHANNELIZING LINE	
								99			828	10400	99	LIN FT	STOP LINE	
								160			828	10600	160	LIN FT	TRANSVERSE LINE	
								2			828	20300	2	EACH	LANE ARROW	
								2			828	20400	2	EACH	WORD ON PAVEMENT, 72"	
															MAINTENANCE OF TRAFFIC	
			80								614	11100	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
		40									614	12460	40	EACH	WORK ZONE MARKING SIGN	
		25									SPECIAL	61412500	25	SQ FT	REPLACEMENT SIGN	13
		25									614	13000	25	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
			10								614	13302	10	EACH	BARRIER REFLECTOR, TYPE B2	
			10								614	13350	10	EACH	OBJECT MARKER	
		1.5									614	22100	1.5	MILE	TEMPORARY EDGE LINE, CLASS I, 642 PAINT	
		0.5									614	22200	0.5	MILE	TEMPORARY EDGE LINE, CLASS I, 740.06, TYPE I	
		LUMP									614	18002	LUMP		MAINTAINING TRAFFIC, MISC.: TRAFFIC CONTROL PLANNING AND IMPLEMENTATION	13
		LUMP		LUMP							615	10000	LUMP		TEMPORARY ROAD	
					LUMP						615	10001	LUMP		TEMPORARY ROAD, AS PER PLAN	20
					112						615	20001	112	SQ YD	TEMPORARY PAVEMENT, CLASS A, AS PER PLAN	20
		50		180							615	25000	230	SQ YD	TEMPORARY PAVEMENT, CLASS B	
			60								616	10000	60	M GAL	WATER	
			6								616	20000	6	TON	CALCIUM CHLORIDE	
		200									622	40020	200	LIN FT	PORTABLE CONCRETE BARRIER, 32"	
2											SPECIAL	69086000	2	EACH	CELLULAR PHONE	8
											614	11000	LUMP		MAINTAINING TRAFFIC	
											623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
											624	10000	LUMP		MOBILIZATION	
											806	16010	12	MONTH	FIELD OFFICE, TYPE B	

CALCULATED

CHECKED

GENERAL SUMMARY

LAK-615-1.26

I:\PROJECTS\Pid12790\dgn\12790gga.dgn 08-NOV-2000 11:07AM jgrmovse