

I:\PROJECTS\12790\dgn\12790gsa.dgn 06-NOV-2000 11:36AM jgr:mov:se

DRAINAGE QUANTITIES								
REF. NO.	LOCATION	SIDE	STATION		605		605	603
			FROM	TO	6" SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP	AGGREGATE DRAINS	6" CONDUIT TYPE F	
			LIN. FT.					LIN. FT.
U-1	CENTER	LT	10+35	11+75	140			10
U-2	CENTER	RT	10+35	11+75	140			10
U-3	CENTER/KING.	LT	10+35	9+38	70			10
U-4	CENTER	RT	9+00	10+35	135			10
U-5	CENTER/KING.	LT	9+00	9+38	76			10
U-6	CENTER	RT	5+50	9+00	350			10
U-7	CENTER	LT	6+00	9+00	300			10
U-8	CENTER	RT/LT	7+50		36			10
U-9	CENTER	LT	5+50	6+00	50			10
U-10	CENTER	RT	4+50	5+50	100			10
U-11	CENTER	LT	4+50	5+50	100			10
U-12	CENTER	RT/LT	4+50	4+85	50			10
U-13	CENTER	LT	3+75	4+50	75			10
U-14	CENTER	RT	3+00	4+50	150			10
U-15	CENTER	LT	3+00	3+75	75			10
U-16	CENTER	RT/LT	3+00	3+35	50			10
U-17	CENTER	LT	1+35	3+00	165			10
U-18	CENTER	RT	1+50	3+00	153			10
U-19	CENTER	LT	1+10	1+35	37			10
U-20	CENTER	RT/LT	1+35	1+50	65			10
U-21	CENTER	RT	1+50		60			10
CHILLICOTHE (SEE GENERAL NOTES)							600	
BALDWIN (SEE TYPICAL SECTIONS)							200	
U-22	CENTER	RT/LT	5+50	5+60	34			20
TOTAL					2411	800	230	

SHEET NO.	870	203	
	SEEDING & MULCHING	EXCAVATION, NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT
	SQ. YD.	CU. YD.	CU. YD.
CHILLICOTHE/MORLEY FARM			
45	32	0	0
46	211	12	0
47	222	19	1
48	176	6	2
49	125	11	0
50	0	0	0
51	38	70	0
52	151	13	2
53	237	23	0
54	157	20	0
CHILLICOTHE			
55	295	77	31
56	377	106	44
57	378	102	61
58	246	70	32
59	411	95	56
60	443	19	217
61	416	6	428
62	764	19	1100
63	561	23	913
64	928	52	1750
65	657	43	1382
66	989	75	2226
67	696	59	1512
68	1073	90	2199
69	689	50	1251
70	680	60	2821
71	410	20	305
72	359	19	199
73	364	49	126
74	496	155	646
75	333	2	451
76	344	7	414
77	239	61	113
78	228	207	1
79	387	654	0
80	329	422	0
81	273	347	0
82	297	160	4
83	168	77	9
132	CULVERT INLET		
		100	
134	OUTFALL #1		
		241	
TABLE 1			
SUB-TOTAL	15179	3641	18296

SHEET NO.	870	203	
	SEEDING & MULCHING	EXCAVATION, NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT
	SQ. YD.	CU. YD.	CU. YD.
CENTER STREET			
84	432	10	598
85	245	21	237
86	227	117	89
87	340	548	26
88	306	533	11
89	212	187	2
90	168	93	9
91	134	86	16
92	187	70	68
93	247	65	105
94	258	67	122
95	224	81	101
96	177	118	31
97	161	193	3
98	248	342	0
99	525	952	3
100	273	294	3
101	283	149	1
102	172	61	12
103	53	0	0
BALDWIN			
104	250	0	254
105	435	0	509
106	290	1	287
107	391	2	310
108	248	4	162
109	271	10	143
110	289	41	115
111	224	48	28
112	230	34	60
113	240	44	65
114	218	60	38
115	192	58	22
116	164	54	6
117	175	59	4
118	164	54	3
119	69	46	0
KINGWOOD			
120	88	43	0
121	258	219	0
122	254	339	0
SUB-TOTAL	9322	5103	3443
TABLE 1			
SUB-TOTAL	15179	3641	18296
GRAND TOTAL	24501	8744	21739

EARTHWORK / UNDERDRAIN SUB-SUMMARY

LAK-615-1.26

CALCULATED
CHECKED