

842.17 Sidewalk Finish. The concrete shall be struck off after placing with a template and finished with a float to produce a sandy texture.

842.18 Method of Measurement. The volume shall be the number of cubic yards (cubic meters) determined by calculations from plan dimensions, in place, completed and accepted.

Reinforcing steel, supports, mechanical connectors, and tie wires shall be incidental in the price bid for structural concrete.

No deduction will be made for the volume of the reinforcing steel, conduits or structural steel other than beam flanges embedded in deck slabs. No deduction will be made for the volume of any embedded timber or concrete piles.

Superstructure concrete includes the concrete in defluctive parapets not having a metallic railing.

Deck concrete may be measured by either volume or area. The area of concrete shall be based on plan dimensions.

842.19 Basis of Payment. Payment will be made at contract prices for:

Item	Unit	Description
842	Cubic yard (cubic meter)	Class ___ concrete, _____
842	Cubic yard (Cubic meter), Square yard (square meter)	Class ___ concrete, bridge deck