

fertilize any area this inspection identifies without a uniform density of at least 70 percent grass cover.

Seeded areas damaged by traffic or erosion, due to no fault or negligence of the Contractor, shall also be regraded, refertilized, reseeded and remulched.

The Contractor shall be compensated for the above work and mobilization and demobilization by supplemental agreement.

870.26 Basis of Payment. Payment for accepted quantities will be made at contract prices for:

Item	Unit	Description
870	Each	Soil analysis test
870	Cubic yard (cubic meter)	Placing topsoil
870	Ton (kilogram)	Commercial fertilizer
870	Ton (kilogram)	Agricultural lime
870	Square yard (square meter)	Seeding and mulching
870	Square yard (square meter)	Repair seeding and mulching
870	M Gallons (cubic meters)	Water
870	Square yard (square meter)	Inter-seeding
870	M Square feet (square meter)	Mowing