

CALC. VLW  
BY 4/5/85  
DATE  
CHKD. WDB  
BY 4/13/85  
DATE

LAK - 615 - 2.82

OHIO  
FHWA  
REGION 5

36  
199

# PAVEMENT REPAIR SUB-SUMMARY

FOR PLAN VIEWS SEE SHEETS 58 THRU 81  
FOR CROSS SECTIONS SEE SHEETS 82 THRU 129

PAVEMENT REPAIR						253	255	255
STREET	SHEET	REF	STATION TO STATION	LENGTH (FEET)	WIDTH (FEET)	PAVEMENT REPAIR SQ.YD.	FULL DEPTH PAVEMENT SAWING L.F.	FULL DEPTH PAVEMENT REMOVAL & RIGID REPLACEMENT, CLASS MS SQ.YD.
S.R.84	58	PR-1	STA.124+63 TO STA.125+13	17	29.5		80	55.7
S.R.84	58	PR-2	STA.155+35 TO STA.156+20	12	29.5		59	39.3
S.R.84	58A	PR-1	STA.129+50 TO STA.130+00	50	2		52	11
S.R.84	58B	PR-1	STA.130+00 TO STA.134+00	400	2		400	89
S.R.84	59	PR-1	STA.134+00 TO STA.138+00	400	2		400	89
S.R.84	60	PR-1	STA.138+00 TO STA.142+00	400	3		400	133
S.R.84	61	PR-1	STA.142+00 TO STA.146+00	400	4		400	178
S.R.84	62	PR-1	STA.146+00 TO STA.150+00	400	4		400	178
S.R.84	63	PR-1	STA.150+00 TO STA.154+00	400	4		400	178
S.R.84	64	PR-1	STA.154+00 TO STA.155+35	135	4		135	60
S.R.84	64	PR-2	STA.155+35 TO STA.156+20	85	3		85	28
S.R.84	64	PR-3	STA.156+20 TO STA.157+55	135	5		135	75
S.R.84	64	PR-4	STA.157+55 TO STA.158+00	45	8.5		90	43
S.R.84	65	PR-1	STA.158+00 TO STA.159+50	150	11.5		300	192
S.R.84	65	PR-2	STA.159+50 TO STA.161+05	155	13		160	224
S.R.84	65	PR-3	STA.161+31 TO STA.161+69	38	3.5			15
S.R.84	65	PR-4	STA.161+29 TO STA.162+00	53	6		72	35
S.R.84	65	PR-5	STA.161+05 TO STA.161+25	20	5		40	11
S.R.615	66	PR-1	STA.7+70 TO STA.7+90	18	5		24	10
S.R.615	66	PR-2	STA.7+80	20	4		40	9
S.R.615	67	PR-1	STA.9+32 TO STA.9+42	23	4		46	10
S.R.615	67	PR-2	STA.9+30 TO STA.9+78	50	4		53	22
S.R.615	67	PR-3	STA.9+78 TO STA.10+12	25	8		50	22
S.R.615	75	PR-1	STA.33+79 TO STA.34+45	65	6		136	43
S.R.615	75	PR-2	STA.33+79 TO STA.34+10	31	6		58	21
S.R.615	75	PR-3	STA.34+00	10	12		24	13
FORESTMEW	80	PR-1	STA.12+15 TO STA.12+40	32	4	14	64	
ESTHER	81	PR-1	STA.11+20 TO STA.11+47	27	5	15	54	
ESTHER	81	PR-2	STA.11+38	4	4	2	8	
TOTALS						31	4165	1784

QUANTITIES CARRIED TO GENERAL SUMMARY

SUBSUMMS.DWG - LAYER 006